

SUMMARY OF QUANTITIES

IDOT CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL	J000-2A	X028-2A	X071-2A	Y007	Y031-/F			Y030-/E	Y000	Y002
				ROADWAY	PEDESTRIAN TUNNEL & WEST WALLS	STRUCTURES		TRAFFIC SIGNALS			LIGHTING	NAPERVILLE UTILITIES	SIGNING
				90% STATE, 10% DUPAGE COUNTY & NAPERVILLE		BRIDGE	NORTHEAST & SOUTHEAST RETAINING WALLS	75TH & WASHINGTON	WASHINGTON & HOBSON	TRAFFIC SIGNAL INTERCONNECT			
FUNDING	STP	STP/TCM	HBRRP	STP	STP	STP	STP	STP	STP	NON-PARTICIPATING	STP		
XX000504	RESTORATION WORK	L SUM	1									1 E	
* XX001051	WATER SERVICE LINE RECONNECTION	EACH	2									2	
XX001429	FORM LINER TEXTURED SURFACE	SQ YD	2259		776	210	1273						
XX002007	AGGREGATE BICYCLE PATH	SQ YD	424	424									
* XX003216	UNIT DUCT, WITH 3-1/C NO. 6 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	13122							13122			
XX003308	TRENCH DRAIN	FOOT	14	14									
XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	340									340 E	
* XX007596	CONDUIT IN TRENCH TRANSITION AND TRANSPOSING	EACH	4									4 E	
* XX004809	UNDER BRIDGE CONDUIT SYSTEM	L SUM	1									1 E	
XX005049	POWER PEDESTAL	EACH	3									3 E	
* XX005307	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED AND BURLAPPED	EACH	6	6									
* XX005480	DUCTILE IRON WATER MAIN, 16", RESTRAINED JOINT TYPE	FOOT	132									132 W	
* XX007593	MANHOLE INSTALLATION, TYPE "A"	EACH	8									8 E	
* XX007594	MANHOLE INSTALLATION, TYPE "G"	EACH	8									8 E	
* XX007595	MANHOLE INSTALLATION, TYPE "E"	EACH	1									1 E	
* XX005581	VIDEO TAPE	UNIT	1									1 E	
* XX005592	NEW PHASE 1 TRANSFORMER VAULT	EACH	7									7 E	
* XX005593	NEW SWITCH GEAR VAULT	EACH	5									5 E	
* XX005594	FA - 2 ENCASEMENT	CU YD	725									725 E	
* XX005595	TRENCH BACKFILL CA-6	CU YD	1250									1250 E	
* XX005597	ROD AND MANDREL	FOOT	32000									32000E	
XX005600	COUNTERPOISE, UNPAVED	FOOT	1100									1100 E	
XX005601	COUNTERPOISE, PAVED	FOOT	200									200 E	
XX005602	HAND DIGGING 0 FT TO 5 FT IN PAVEMENT	CU YD	40									40 E	
XX005603	HAND DIGGING 5 FT TO 20 FT IN PAVEMENT	CU YD	30									30 E	
XX005604	HAND DIGGING 0 FT TO 5 FT IN UNPAVED AREAS	CU YD	40									40 E	
XX005605	HAND DIGGING 5 FT TO 20 FT IN UNPAVED AREAS	CU YD	30									30 E	
* XX005937	L.E.D. INTERNALLY ILLUMINATED STREET NAME SIGN	EACH	7	7									

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-00114-00-PV	DUPAGE	563	17
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63024	

LEGEND:


- * SPECIALTY ITEM
- E NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC (NON-PARTICIPATING)
- W NAPERVILLE DEPARTMENT OF PUBLIC UTILITIES - WATER (NON-PARTICIPATING)

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
WASHINGTON STREET - 75th STREET
SUMMARY OF QUANTITIES

SHEET 13 OF 19

CONSULTANT
TYLIN INTERNATIONAL

City of  **Naperville**

DRAWN:	SHEET NO.
CHECKED:	
APPROVED:	
DATE: APRIL 11, 2008	
SCALE: NONE	
JOB NO.: P-91-494-00	PROJECT NO.: M-CMM-700 (985)