F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2552	00-0(14-00-PV	DuPAGE	563	54
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DUPAGE CO FOREST PRESERVE

CONTRACT NO. 63024

MATCHLINE STA. 434+00 - SEE SHEET 1 OF 15

MATCHLINE STA. 448+50 - SEE SHEET 3 OF 15

WASHINGTON STREET

CLYDE DRIVE

HOBSON ROAD

PIONEER PARK

EXISTING 12' SHARED USE PATH

WIDENING AND RESURFACING FULL-DEPTH RECONSTRUCTION

REALIGNED 12' SHARED USE PATH

℄ NB WASHINGTON

℄ SB WASHINGTON

EXISTING ℄ WASHINGTON ST.

CCC&G, TYPE B-6.12

CCC&G, TYPE B-6.24 (TYP)

5" PC CONC SIDEWALK

CURB TRANSITION (PAID FOR AS CCC&G, TYPE B-6.24)

CONCRETE MEDIAN

LANDSCAPED MEDIAN (SEE LANSCAPING PLANS)

TEMP EASEMENT

EX ROW

104' TAPER (52:1)

121' TAPER (41:1)

225' TAPER (84:1)

217.5' TAPER (50:1)

165' TAPER (15:1)

242' TAPER(11:1)

PROPOSED GUARDRAIL (SEE SHEET 9 OF 11)

LIMIT OF WORK ON HOBSON ROAD

SEE INTERSECTION LAYOUT DETAILS SHEET (WASHINGTON ST. & HOBSON RD.)

STA 446+39.28 ℄ NB WASHINGTON ST = STA 700+00.00 ℄ HOBSON RD

FOR SOUTHBOUND PROFILE SEE DRAWING 12 OF 13

HORIZONTAL SCALE: 1" = 50'-0"

VERTICAL SCALE: 1" = 5'-0"

LOCATION MAP

PROPOSED PROFILE NB ℄ WASHINGTON

EXISTING GROUND ℄ NB WASHINGTON

VPI STA. 440+60.00 ELEVATION 662.90 ex = 0.12' K = 146 120.00' V.C.

VPI STA. 446+25.00 ELEVATION 665.22 ex = -0.14' K = 129 120.00' V.C.

VPI STA. 448+00.00 ELEVATION 664.31 ex = 0.17' K = 128 130.00' V.C.

| EXISTING & PROP NB ℄ PROFILE ELEVATIONS | 665.62 | 665.04 | 665.52 | 664.89 | 665.42 | 664.70 | 665.31 | 664.51 | 665.21 | 664.42 | 665.11 | 664.32 | 665.01 | 664.22 | 664.90 | 664.11 | 664.80 | 664.13 | 664.70 | 664.14 | 664.59 | 664.14 | 664.49 | 664.02 | 664.39 | 664.03 | 664.28 | 663.95 | 664.18 | 663.91 | 664.08 | 663.86 | 663.97 | 663.77 | 663.87 | 663.68 | 663.77 | 663.59 | 663.66 | 663.48 | 663.56 | 663.41 | 663.46 | 663.33 | 663.35 | 663.26 | 663.25 | 663.18 | 663.15 | 663.17 | 663.07 | 663.17 | 663.03 | 663.21 | 663.03 | 663.27 | 663.08 | 663.17 | 663.30 | 663.27 | 663.42 | 663.37 | 663.61 | 663.47 | 663.69 | 663.58 | 663.76 | 663.68 | 663.85 | 663.78 | 663.82 | 663.89 | 663.89 | 663.99 | 663.99 | 664.09 |
|---|---|---|---|---