



SCHEDULE OF INTERCONNECT QUANTITIES

81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2202
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	500
81400100	HANDHOLE	EACH	11
81900200	TRENCH AND BACKFILL FOR ELECTRIC WORK	FOOT	2202
87900200	DRILL EXISTING HANDHOLE	EACH	2
89502380	REMOVE EXISTING HANDHOLE	EACH	6
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14-1C	FOOT	7864
X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F, SM12F	FOOT	7864

INTERCONNECT SCHEMATIC LEGEND

EXISTING	PROPOSED	EXISTING	PROPOSED

REVISIONS	
NAME	DATE

INTERSECTION IMPROVEMENT
 WASHINGTON STREET - 75th STREET
 INTERCONNECT SCHEMATIC,
 SCHEDULE OF QUANTITIES
 75TH ST. AND WASHINGTON ST.
 SHEET 5 OF 5

CONSULTANT
TYLIN INTERNATIONAL

City of **Naperville**

DRAWN: CBS
 CHECKED: DAJ
 APPROVED:
 DATE: APRIL 11, 2008
 SCALE: NONE
 JOB NO.: P-91-494-00

SHEET NO.
 PROJECT NO.: M-CMM-7003 (985)