

F.A. RTE. 2552	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	00-0014-00-PV	DUPAGE	563	313
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT 63024				

PLANTING TREES, SHRUBS, AND EVERGREENS 3" TO 5" DIA., 6" TO 8" DIA., 9" TO 11" DIA. AND 12" TO 15" DIA.

THIS WORK SHALL CONSIST OF PLANTING TREES, SHRUBS AND EVERGREENS OF VARIOUS SIZES AND TRUNK DIAMETERS. THE CONTRACTOR SHALL CAREFULLY EXAMINE THE PROPOSED LOCATION FOR FOREIGN UTILITIES, ROOM FOR GROWTH, SUITABLE DRAINAGE AND SUNLIGHT OR SHADE. THE ARBORIST SHALL BE ON THE PROJECT DURING THE ENTIRE PROCESS AND SHALL DIRECT THE PLANTING.

PRIOR TO PLANTING, EXAMINE THE AREA FOR OVERHEAD OBSTRUCTIONS WHEN DIGGING AND MOVING. CONTRACTOR SHALL UNDERTAKE ANY PRUNING REQUIRED REMOVING POORLY POSITIONED OR DAMAGED LIMBS. THE CONTRACTOR SHALL IDENTIFY IF THE SPECIES, OR SOME PORTION THEREOF, IS DISEASED. THE CONTRACTOR SHALL DETERMINE IF THE TREE OR EVERGREEN IS A SAFETY CONCERN PRIOR TO PERFORMING ANY WORK. FOR EXAMPLE, IF IT CREATES A LINE OF SIGHT PROBLEM FOR VEHICLES. IF IN THE OPINION OF THE ARBORIST THE TREE OR EVERGREEN IS NOT PLANTABLE THEN THE TREE SHALL NOT BE PLANTED. CONTRACTOR SHALL EXAMINE THE NEW SITE FOR THE TREE'S HABITAT REQUIREMENTS. FOR EXAMPLE: WIND PROTECTION: TIME OF YEAR, SOIL PH, SUNLIGHT, DRAINAGE AND MOISTURE REQUIREMENTS. PLANT IN EARLY FALL, BEFORE FIRST FREEZE OR IN THE SPRING BEFORE THE BUDS ON THE TREES OR EVERGREENS BEGIN TO SWELL.

THE CONTRACTOR SHALL BE REQUESTED TO PLANT THE FOLLOWING TREE SPECIES:

USE 15 GALLON SIZE OR 4 FEET HIGH OR 4" DIAMETER AS APPLICABLE.

RIVER BIRCH	SARGENT CRAB TREE
HACKBERRY	NINE BARK DARTS GOLD
HAWTHORN	SUMAC SMOOTH
LINDEN AMERICAN	ARROW WOOD VIBURNUM
MAPLE SILVER	WIEGELA FLORIDA
MAPLE NORWAY	CLEVELAND PEAR
OAK PIN	JAPANESE YEW
RED OAK	SUMATRAN YEW
ASH GREEN	ARBORVITAE GLOBE
SUMAC	ARBORVITAE TECHNY
COLORADO SPRUCE	ARBORVITAE AMERICAN
BALSAM	MUGHO PIVE
SPRUCE	BOXWOOD WINTERGREEN
PINES OF VARIOUS SPECIES	DWARF RED BUCK EYE

THE CONTRACTOR SHALL PREPARE A DESIGN OF THE PLANTED TREE AS IT FITS ON THE PROPERTY BY AN ARCHITECT LANDSCAPER. THE DRAWING SHALL BE GIVEN TO THE ENGINEER.

THE CONTRACTOR SHALL GET APPROVAL FOR PLANTING FROM THE CITY OF NAPERVILLE PRIOR TO PLANTING.

THE CONTRACTOR SHALL IDENTIFY WHAT TYPE OF TREE SHALL BE PLANTED AND PREPARE TREE FOR SHIPPING AND PLANTING

THE CONTRACTOR SHALL MAINTAIN ALL ACTIVITIES WITHIN THE EASEMENTS OR PUBLIC WAYS ANY AND ALL OTHER MEANS TO PERFORM THE WORK IS AT THE CONTRACTORS EXPENSE AND SHALL OBTAIN PERMISSION FROM ALL LAND OWNERS TO USE THEIR PROPERTY.

THE CONTRACTOR UNDER THE DIRECTION OF AN ARBORIST SHALL PREPARE THE SITE FOR THE PLANTING, FERTILIZE, WATER, TRIM ADD MULCH, STAKE AS NECESSARY, PROVIDE DRAINAGE AND MAINTAIN FOR ONE YEAR.

TREES, SHRUBS AND EVERGREENS TO BE PLANTED SHALL BE MEASURED IN INCH-DIAMETER. THE DIAMETER WILL BE MEASURED AT A POINT FOUR (4) FEET ABOVE THE HIGHEST GROUND LEVEL AT THE BASE OF THE TREE OR EVERGREEN AND WILL BE DETERMINED BY ASSURING THE CIRCUMFERENCE OF THE TREE AND DIVIDING THIS MEASURED CIRCUMFERENCE BY 3.1416.

THE BASIS OF PAYMENT:

THIS WORK SHALL BE PAID FOR AT THE CONTRACT PRICE FOR EACH TREE SPECIES INSTALLED COMPLETE AND PLANTED, 3 INCHES TO 5 INCHES, 6 INCHES TO 8 INCHES OR 9 INCHES TO 11 INCHES OR 12 INCHES TO 15 INCHES, THIS INCLUDES EXCAVATING, REMOVING BALL, FERTILIZERS, EQUIPMENT OF ALL TYPES, HAULING, LOADING, UNLOADING, TRAFFIC CONTROL, STORAGE, NEW 6" INCH LAYER OF BLACK DIRT, MULCH, EDGING, STAKING, REMOVE ALL EXCAVATED MATERIAL OFF SITE, REMOVING AND INSTALLING FENCES, TEMPORARY WORK TO GET TO SITE, SETTING AND ALIGNING, PROVIDE TREES WITH ALL WATERING AND FERTILIZER AS REQUIRED, WITH MAINTENANCE AND ONE-YEAR GUARANTEE FROM LAST PAYMENT FOR THE ENTIRE PROJECT.

NAPERVILLE PUBLIC UTILITIES DEPARTMENT	PLANTING TREES, SHRUBS, AND EVERGREENS 3" TO 5" DIA., 6" TO 8" DIA., 9" TO 11" DIA. AND 12" TO 15" DIA.	DATE: 05-01-05 Page 1 of 1 56270-1210
ELECTRIC STANDARDS		

WF# INFORMATION		CITY OF NAPERVILLE/DEPARTMENT OF PUBLIC UTILITIES - ELECTRIC			
WF# 59481 WASHINGTON ST. 75TH TO OLYMPUS DR. EAST SIDE	JOB 1 EU-73	CALL J.U.L.I.E. 48 HRS. PRIOR TO CONSTRUCTION			
WF# 59482 75TH WASHINGTON ST. TO OLYMPUS DR. NORTH SIDE	JOB 2 EU-73	PROJECT TITLE 75TH ST. AND WASHINGTON ST. ROAD IMPROVEMENTS	MAP NO.: -	CAD FILE 0056270001072.DWG	
WF# 59484 75TH WASHINGTON ST. TO CLYDE DR. SOUTH SIDE	JOB 3 EU-73	PROJECT DESCRIPTION TRENCH SECTION DETAILS	DRAWN BY: JK, PM	PROJECT NO.: EU12-06-03 EU73	COMPLETED BY:
WF# 59485 WASHINGTON ST. 75TH TO BAILEY RD. EAST SIDE	JOB 4 EU-73	DATE 4-01-08	WORK REQUEST NO. 56270	CHRG:	SBC:
	ENGINEER RPS	ISSUED	APR:	SCALE: NTS	SHEET 72 OF 73
	REVISION	1	2	3	