



**DETAIL A**

**NOTES:**

1. See Sheet 18 for Superstructure Details and Bill of Material.
2. Bars indicated thus 20x3-#5 etc. indicates 20 lines of bars with 3 lengths per line.
3. See Sheet 17 for Parapet Reinforcement.
4. Dimensions are based on a Rolled Rail Strip Seal Joint. If the Contractor elects to use the Welded Rail Strip Seal Joint, deck dimensions may require adjustments to satisfy the details on Sheet 20.
5. Cut longitudinal bars to clear drainage scuppers.
6. Cut longitudinal b(E) bars in median at aluminum sheet locations.
7. For Section A-A, see Sheet 16.

**TYLIN INTERNATIONAL**

DESIGNED	PL
CHECKED	SP
DRAWN	PL
CHECKED	SP

**PLAN**

**MINIMUM BAR LAPS**

Bar	Lap
#5	2'-2"
#6	2'-7"
#7	3'-5"

REVISIONS	
NAME	DATE

**DECK PLAN - NORTH HALF**

75th STREET OVER THE  
WEST BRANCH OF THE DUPAGE RIVER  
FAP 369  
SECTION 00-00114-00-PV STA. 151+38.03  
DUPAGE COUNTY  
S.N. 022-3118