

F. A. P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
29	08-00055-00-LT	COOK	012	002
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #63028

ALL ITEMS TO BE TYPE CODE Y030-1E

SUMMARY OF QUANTITIES				
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4500
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200
	25200200	SUPPLEMENTAL WATERING	UNIT	95
	25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	4500
	44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	500
	67100100	MOBILIZATION	L SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	80400100	ELECTRIC SERVICE INSTALLATION	EACH	3
	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	2915
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	225
	81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	14100
	81701325	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C NO. 1/0	FOOT	200
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	10980
	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	790
	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	40
	84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	60
	84200700	LIGHTING FOUNDATION REMOVAL	EACH	60
	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	3
	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	3
	X8380090	BREAKAWAY DEVICE, COUPLING	EACH	328
	XX000596	FESTOON OUTLET	EACH	82
	XX001579	LIGHTING CONTROLLER, CONSOLE TYPE	EACH	3
	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	85
△	Z0076600	TRAINEES	HOUR	500
	XX007577	HMA PARKWAY REMOVAL AND REPLACEMENT	SQ YD	50
	XX007578	LIGHT POLE, STEEL, TAPERED ROUND, 34 FT. M.H. 8 FT. MAST ARM (SPECIAL)	EACH	82
	XX007487	LUMINAIRE, SODIUM VAPOR, 250 WATT, (SPECIAL)	EACH	82
*	XX007579	PAINT EXISTING LIGHTING UNIT	EACH	8

\* - INDICATES SPECIALTY ITEMS  
△ - Y080

GENERAL NOTES

- ALL WORK TO CONFORM TO THE NATIONAL ELECTRICAL CODE AND ANY APPLICABLE LOCAL CODES.
- CONTRACTOR TO VERIFY LOCATION OF ALL UNDERGROUND UTILITIES BEFORE TRENCHING OR AUGERING.
- BEFORE INSTALLING STANDARDS NEAR OVERHEAD FACILITIES CALL C.E. Co. FOR APPROVAL OF LOCATION.
- FOR LOCATION OF EXISTING UNDERGROUND ELECTRICAL CABLE CALL C.E. Co.
- SIZE ALL CONDUIT AS SPECIFIED ON DRAWINGS.
- CONTRACTOR SHALL TAKE ALL NECESSARY MEASURES TO RESTORE ANY SPECIALIZED LANDSCAPING, (i.e. DECORATIVE ROCKS, SHRUBS, PLANTS, ECT.) OR SHALL REPLACE IT, THE COST OF WHICH SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

95TH STREET  
STREET LIGHTING PLAN  
SUMMARY OF QUANTITIES AND  
GENERAL NOTES

SCALE: VERT. NA  
HORIZ. NA  
DATE 07/15/08  
DRAWN BY AG  
CHECKED BY PAP