SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1000	
				RINGWOOD ROAD	BARNARD MILL ROAD
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	151	48	103
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,254	4,461	793
40600300	AGGREGATE (PRIME COAT)	TON	111	94	17
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	502	502	0
40600895	CONSTRUCTING TEST STRIP	EACH	3	2	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	939	819	120
40600990	TEMPORARY RAMP	SQ YD	876	720	156
40603310	HOT-MIX ASPHALT SURFACE COURSE,MIX "C", N50	TON	686	0	686
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50	TON	2,647	2,621	26
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	756	216	540
42400800	DETECTABLE WARNINGS	SQ FT	136	40	96
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	20,259	12,339	7,920
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	100	200
44004700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	687	216	471
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	27	9	18
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	53	19	34
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	69	19	50
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	131	48	83
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	38	26	12
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	76	54	22
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	88	54	34
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	192	135	57
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	23	23	0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	46	46	0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	46	46	0
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	115	115	0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10,492	8,367	2,125
48101200	AGGREGATE SHOULDERS, TYPE B	TON	706	706	0
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	0	3
64200105	SHOULDER RUMBLE STRIP	FOOT	560	560	0

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 1000	
				RINGWOOD ROAD	BARNARD MILL ROAD
67100100	MOBILIZATION	LSUM	1	0.79	0.21
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1	0.79	0.21
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,680	3,880	800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,574	1,304	270
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	274	183	91
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34,549	30,245	4,304
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,476	646	830
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	450	250
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	94	32	62
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2	0	2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2	0	2
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	220	220	0
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	4	2	2
XX005924	TEMPORARY RAMP REMOVAL	SQ YD	876	720	156
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	156	104	52
X4420450	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	47	0	47
X4420452	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	94	0	94
X4420454	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	142	0	142
X4420456	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	189	0	189

* INDICATES SPECIALTY ITEM

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	AREA (SQ YD)
RINGWOOD ROAD (STA 75+35)	35
RINGWOOD ROAD (STA 111+34)	30
RINGWOOD ROAD (STA 112+39)	135
PRAIRIE RIDGE (STA 129+59)	167
PIONEER OAKS (STA 147+42)	167
RINGWOOD ROAD (STA 160+06)	85
DRIVEWAYS (STA 112+39 TO STA 156+00)	200
BARNARD MILL ROAD (STA 199+40)	35
BARNARD MILL ROAD (STA 221+39)	85
TOTAL	939

*F.A.U. 0166 RINGWOOD ROAD AND F.A.U. 4083 BARNARD MILL ROAD

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001127 EXPIRES 4/30/2009
WEBSITE - WWW.BAXTERWOODMAN.COM
...\pdotdrive\OCZ 9600.crv
...\CADD Support\IDOT\IDOT08.tbl
in:\chgo\080606-rmpport-pdr\cadd-survey\dr-cwings\dgns\080606-S00.sht
6/27/2008 8:09:50 AM CST

BAXTER & WOODMAN Consulting Engineers

USER NAME = 418cjc	DESIGNED - RWL	REVISED -5/28/08 - IDOT REVIEW	
	DRAWN - CJC	REVISED -6/27/08 - IDOT REVIEW	
FILE NAME = 080606-S00.sht	CHECKED - RWL	REVISED -	
PLOT DATE = 6/27/2008	DATE - 3/28/08	REVISED -	

VILLAGE OF RINGWOOD, ILLINOIS
RINGWOOD ROAD AND
BARNARD MILL ROAD STP (LAPP)
IMPROVEMENTS

SUMMARY OF QUANTITIES AND SCHEDULE OF QUANTITIES

SCALE: NONE | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	08-00002-00-RS	McHENRY	24	3
FED. ROAD DIST. NO.		CONTRACT NO. 63056		
C-91-225-08	ILLINOIS	FED. AID PROJECT M-8003(961)		