

HSIP
90% FED
10% STATE
URBAN

| | | | | |
|---------------------|-----------------|---------------------------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 326 | (111CS) W&RS-21 | RUNDY | 85 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

| FAP 326 (IL ROUTE 47) | | | | CONSTRUCTION TYPE CODE | | |
|-----------------------|---|-------|--------|------------------------|---------|------|
| SUMMARY OF QUANTITIES | | | | RWY | TS | TS |
| CODE NO. | ITEM | UNIT | TOTAL | I000-2A | Y031-1F | ● |
| X0355800 | STORM SEWER WATER MAIN 24" | FOOT | 68 | 68 | | |
| X0930400 | STORM SEWER WATER MAIN 12" | FOOT | 303 | 303 | ▲ | |
| * X8710020 | FIBER OPTIC IN CONDUIT, NO 62.5/125 MM12F SM12F | FOOT | 5220 | | 5220 | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | |
| * XX002852 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM | EACH | 1 | | 1 | |
| XX005565 | REMOVE AND RESET BRICK PAVERS | SQ FT | 289.9 | 289.9 | | |
| * XX006661 | UNINTERRUPTABLE POWER SUPPLY | EACH | 3 | | 3 | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS | SQ FT | 405.6 | 405.6 | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 4149.2 | 4149.2 | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 4310.6 | 4310.6 | | |
| 70300250 | TEMPORARY PAVEMENT MARKING - LINE 8" | FOOT | 826.3 | 826.3 | | |
| 70300260 | TEMPORARY PAVEMENT MARKING - LINE 12" | FOOT | 657.2 | 657.2 | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 458.4 | 458.4 | | |
| 42400410 | PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH | SQ FT | 797 | 797 | | |
| X0930500 | STORM SEWER WATER MAIN 18" | FOOT | 40 | 40 | ▲ | |
| 59300100 | CONTROLLED LOW-STRENGTH MATERIAL | CU YD | 309 | 309 | | |
| * X0325961 | TRACER CABLE NO. 14 1/C | FOOT | 5220 | | 5220 | |
| * ● 88700200 | LIGHT DETECTOR | EACH | 8 | | | 8 |
| * ● 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 2 | | | 2 |
| * ● X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 3812 | | | 3812 |

● NON-PARTICIPATING ITEMS - CITY OF MORRIS PAYS 100% Y031-3D

* SPECIALTY ITEM

▲ REVISED 9-3-08

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL ROUTE 47
GRUNDY COUNTY

SCALE: NONE
DATE: 09/2007

DRAWN BY: KHH
CHECKED BY: FML

27 MAR 08