

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(111CS) W&RS-21	GRUNDY	85	9
STA. TO STA.		FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		

40603570 - POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90			
LOCATION		QUANTITY	
ALIGNMENT	STATION TO STATION	TONS	
IL 47	10+56.3 31+10.0	1145	
BENTON	10+00.0 11+34.2	56	
TOTAL		1201	

40800050 INCIDENTAL HOT MIX ASPHALT SURFACING		
ALIGNMENT	OFFSET OF MAINLINE	TON
MAIN	EAST	15.3
	WEST	23.8
JEFFERSON	EAST	22.8
	WEST	27.2
JACKSON	EAST	25.4
	WEST	18.8
NORTH	EAST	38.5
	WEST	41.8
CHAPIN	EAST	22.3
	WEST	28.2
BENTON	WEST	60.3
TOTAL		324.4

42001300 PROTECTIVE COAT		QUANTITY
ITEM		SQ. YD.
COMBINATION CONCRETE CURB & GUTTER		1118.2
HOT MIX ASPHALT RESURFACING		16616.1
PCC DRIVEWAY PAVEMENT		393.6
PCC SIDEWALK & RAMPS		1521.9
ISLAND PAVEMENT		40.5
TOTAL		19690.3

42300200 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		
LOCATION	QUANTITY	
STATION	OFFSET	SQ. YD.
13+28.54	RT	30.3
TOTAL		30.3

42300400 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		
LOCATION	QUANTITY	
STATION	OFFSET	SQ. YD.
12+20.97	LT	27.9
12+60.10	RT	37.9
12+69.88	LT	42.4
12+97.76	LT	46.3
16+04.99	LT	33.8
19+35.93	LT	18.2
22+29.62	RT	40.8
22+59.07	LT	26.7
22+59.94	RT	28.5
25+99.24	RT	51.3
WEST	RT	7.4
JEFFERSON	LT	2.0
WEST	LT	30.9
JEFFERSON	LT	30.9
EAST	LT	30.9
NORTH		
TOTAL		394.2

42400100 PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH			
LOCATION	QUANTITY		
STATION TO STATION	OFFSET	SQ. FT.	
11+86.5	12+42.5 RT	290.4	
11+88.7	12+05.2 LT	70.2	
12+38.0	12+62.3 LT	97.6	
12+77.7	13+14.5 RT	178.9	
12+77.4	12+88.0 LT	29.0	
13+07.5	14+14.8 LT	617.9	
13+42.5	14+17.5 RT	452.1	
14+59.7	15+95.6 LT	770.5	
14+59.6	15+23.3 RT	442.0	
16+12.1	17+50.3 LT	787.4	
17+20.6	17+55.2 RT	255.4	
17+97.8	18+34.5 RT	140.0	
17+95.3	19+29.4 LT	744.3	
19+42.4	20+78.0 LT	817.2	
19+74.7	20+74.3 RT	687.2	
21+18.6	22+53.6 LT	787.7	
21+25.9	22+17.2 RT	570.5	
22+42.0	22+54.3 RT	36.2	
22+64.5	24+02.9 LT	774.1	
22+65.0	24+07.8 RT	763.4	
24+54.6	24+66.9 LT	98.0	
24+48.8	25+81.0 RT	754.8	
26+17.5	27+35.7 RT	766.7	
27+02.3	27+42.2 LT	377.8	
28+01.0	30+93.7 LT	1561.7	
28+01.9	30+93.7 RT	1686.4	
TOTAL		14557.4	

42400420 PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH SPECIAL			
LOCATION	QUANTITY		
STATION TO STATION	OFFSET	SQ. FT.	
16+12.38	17+41.20 LT	773.9	
21+24.77	22+53.61 LT	811.8	
22+65.74	23+97.50 RT	788.4	
TOTAL		2374.1	

44000200 DRIVEWAY PAVEMENT REMOVAL		
LOCATION	QUANTITY	
STATION	OFFSET	SQ. YD.
12+20.97	LT	31.3
12+60.10	RT	40.7
12+69.88	LT	41.4
12+97.76	LT	49.9
13+28.54	RT	38.4
16+04.99	LT	42.7
19+35.93	LT	25.9
21+73.37	RT	50.3
22+29.62	RT	69.6
22+59.07	LT	27.3
22+59.94	RT	30.2
25+99.24	RT	73.6
WEST	RT	6.8
JEFFERSON	LT	1.7
WEST	LT	31.2
JEFFERSON	LT	31.2
EAST	LT	31.2
NORTH		
TOTAL		561.0

42400800 DETECTABLE WARNINGS		
INTERSECTION	CORNER	SQ. FT.
JEFFERSON	SW	20
JEFFERSON	SE	20
JEFFERSON	NE	20
JEFFERSON	NW	20
JACKSON	SW	20
JACKSON	NW	20
JACKSON	SE	20
JACKSON	NE	20
NORTH	SW	20
NORTH	SE	20
NORTH	NE	20
NORTH	NW	20
CHAPIN	SW	20
CHAPIN	SE	20
CHAPIN	NE	20
CHAPIN	NW	20
BENTON	SW	14.2
BENTON	SE	12.0
BENTON	NE	11.3
BENTON	NW	10.1
BENTON	W. ISLAND	32.8
BENTON	E. ISLAND	33.7
TOTAL		434.1

44000100 PAVEMENT REMOVAL		
LOCATION	QUANTITY	
STATION TO STATION	OFFSET	SQ. YD.
13+08	14+00 LT	35.1
14+73	17+37 LT	102.7
NW QUAD. OF JACKSON ST.		60.8
TOTAL		198.6

44000198 HMA SURFACE REMOVAL, VARIABLE DEPTH			
ALIGNMENT	STATION TO STATION	SQ. YD.	
IL 47	11+86.5 31+10.0	12756.2	
W. JEFFERSON	9+33.7	9+69.0 194.2	
E. JEFFERSON	10+00.0	10+58.8 162.8	
W. JACKSON	9+33.4	9+66.1 181.6	
E. JACKSON	10+00.0	10+50.2 134.0	
W. NORTH	9+19.8	9+68.6 274.8	
E. NORTH	10+00.0	10+92.5 298.5	
W. CHAPIN	9+37.8	9+70.0 201.6	
E. CHAPIN	10+00.0	10+59.0 159.3	
W. BENTON	9+20.0	9+70.0 431.0	
E. BENTON	10+00.0	11+34.2 665.2	
TOTAL		15459.3	

44000500 COMBINATION CURB AND GUTTER REMOVAL			
LOCATION	QUANTITY		
STATION TO STATION	OFFSET	FOOT	
11+88.7	14+16.7 LT	255.2	
11+87.9	14+19.4 RT	249.7	
14+58.1	17+57.7 RT	326.4	
14+57.1	17+52.7 LT	342.4	
17+92.9	20+77.8 LT	348.7	
17+92.9	20+85.2 RT	346.2	
21+18.0	24+04.5 LT	348.0	
24+50.4	27+43.2 LT	343.5	
24+47.0	27+47.7 RT	403.4	
WEST BENTON ISLAND	N/A	79.0	
EAST BENTON ISLAND	N/A	77.5	
28+20.7	31+10.0 CENTER MEDIAN	580.0	
27+97.4	31+10.0 RT	350.2	
27+98.5	31+10.0 LT	332.9	
TOTAL		4383.1	

44000600 SIDEWALK REMOVAL		
LOCATION	QUANTITY	
STATION TO STATION	OFFSET	SQ. FT.
11+88.7	11+94.7 LT	27.9
11+86.5	12+45.2 RT	334.9
12+36.0	12+62.3 LT	130.9
12+75.3	13+14.2 RT	148.5
12+76.1	12+89.6 LT	61.8
13+07.0	14+06.5 LT	448.0
13+39.8	14+08.8 RT	319.7
14+62.7	15+23.5 RT	275.0
14+68.0	15+98.0 LT	602.4
16+13.0	17+41.2 LT	596.8
18+05.0	19+29.2 LT	557.1
19+42.7	20+71.4 LT	601.0
19+74.7	20+75.7 RT	542.5
21+25.5	21+43.4 RT	157.6
21+24.0	22+52.3 LT	604.1
21+79.0	22+05.9 RT	105.5
22+43.7	22+53.7 RT	38.3
22+65.9	23+96.2 RT	573.3
22+64.2	23+99.3 LT	590.6
24+52.6	24+66.9 LT	150.1
24+62.0	25+81.2 RT	605.0
26+17.3	27+41.2 RT	735.8
27+01.5	27+42.3 LT	412.1
27+97.9	30+93.7 RT	1713.9
28+01.1	30+27.2 LT	1551.3
TOTAL		11884.1

44002805 ISLAND REMOVAL	
LOCATION	QUANTITY
	SQ. FT.
WEST BENTON ISLAND	241.0
EAST BENTON ISLAND	252.4
TOTAL	493.4

44003100 MEDIAN REMOVAL		
LOCATION	QUANTITY	
STATION TO STATION	SQ. FT.	
28+21.0	31+10.0	498.8
BENTON W. ISLAND		241.0
BENTON E. ISLAND		252.4
TOTAL	992.2	

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT			
LOCATION	QUANTITY		
STATION TO STATION	OFFSET	FOOT	
11+87.4	14+18.7 LT	254.2	
11+86.5	14+21.3 RT	252.4	
14+56.1	15+74.2 RT	136.1	
14+55.7	17+54.5 LT	350.8	
17+91.1	20+79.8 LT	347.6	
19+74.9	20+81.8 RT	128.4	
21+16.5	24+06.1 LT	342.6	
21+15.3	24+10.6 RT	341.9	
24+48.8	27+45.1 LT	350.6	
24+45.2	27+49.7 RT	409.2	
27+96.5	31+10.0 LT	336.1	
29+95.3	31+10.0 RT	354.4	
TOTAL		3604.4	

44200276 PAVEMENT PATCHING, TYPE II		
LOCATION	QUANTITY	
STATION TO STATION	OFFSET	SQ. YD.
10+63.0	11+67.4 LEFT	87.91
13+96.4	14+03.5 LEFT	44.63
14+02.0	14+62.0 NONE	55.20
17+48.0	17+96.1 LEFT	50.73
18+15.2	18+22.6 NONE	42.49
20+74.9	21+23.8 LEFT	43.74
23+71.2	23+78.6 NONE	42.64
23+97.3	24+49.3 RIGHT	36.83
24+02.4	24+52.2 LEFT	36.75
26+30.4	26+37.0 NONE	39.80
27+14.2	27+28.5 NONE	55.18
27+33.9	27+95.4 RIGHT	53.63
28+21.3	28+28.4 NONE	68.64
29+21.7	29+28.0 NONE	36.48
30+21.2	30+28.5 NONE	42.29
TOTAL		736.94

42400410 PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH		
LOCATION	QUANTITY	
STATION TO STATION	OFFSET	SQ. FT.
10+90.83 BENTON ST.	28+84.87 IL 47	797
TOTAL		797

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES IL ROUTE 47 GRUNDY COUNTY SCALE: NONE DATE: 09/2007 DRAWN BY: KHH CHECKED BY: FML