

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(111CS) W&RS-21	GRUNDY	85	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

55100500, 55100700, 55100900, 55101100, 55101200 STORM SEWER REMOVAL							
STATION			FOOT				
			12"	15"	18"	21"	24"
FROM	TO	OFFSET	55100500	55100700	55100900	55101100	
10+63	12+39	LEFT				175.7	
12+39	12+41	LEFT	5.2				
12+39	14+76	LEFT				237.7	
12+41	12+41	RIGHT	4.3				
14+57	14+76	LEFT	25.4				
14+76	14+88	LEFT	15.1				
14+76	16+21	LEFT			145.5		
16+21	16+30	LEFT	14.3				
16+21	18+19	LEFT			197.9		
17+51	17+98	LEFT	47.3				
17+98	18+19	LEFT	21.8				
18+04	18+19	NONE	74.3				
18+19	18+97	LEFT			78.8		
18+97	19+00	LEFT	9.0				
18+97	20+44	LEFT		146.1			
20+44	20+78	LEFT	41.8				
20+44	21+90	LEFT		146.6			
21+90	22+45	LEFT		57.0			
22+45	23+00	LEFT	55.1				
22+91	22+99	RIGHT	9.1				
26+25	26+33	LEFT	8.3				
26+27	26+35	RIGHT	7.9				
26+33	26+35	NONE	54.9				
26+35	28+07	RIGHT		177.3			
27+97	28+07	RIGHT	16.8				
28+07	28+89	RIGHT		87.7			
28+89	28+90	RIGHT	72.2				
28+89	29+50	RIGHT			60.5		
28+90	28+90	NONE	55.2				
29+50	31+30	RIGHT				180.1	
TOTAL			538.0	614.7	482.7	413.4	180.1

60235700, 60240220 INLETS			
LOCATION		EACH	
		TYPE A TYPE 3 FRAME AND GRATE	TYPE B TYPE 3 FRAME AND GRATE
STATION	OFFSET	60235700	60240220
12+39	RIGHT	1	
14+00	RIGHT	1	
14+61	LEFT	1	
14+61	RIGHT	1	
15+75	LEFT	1	
15+75	RIGHT	1	
17+24	RIGHT	1	
17+26	LEFT	1	
17+96	LEFT	1	
18+19	RIGHT	1	
19+00	RIGHT		1
20+00	LEFT	1	
20+00	RIGHT	1	
22+47	LEFT	1	
22+50	RIGHT	1	
23+00	RIGHT		1
23+75	RIGHT		1
24+01	LEFT		1
24+50	RIGHT	1	
24+54	LEFT	1	
25+25	LEFT	1	
25+25	RIGHT	1	
26+27	RIGHT		1
27+25	LEFT	1	
28+25	LEFT	1	
28+25	RIGHT		1
29+25	LEFT	1	
29+25	RIGHT		1
30+25	LEFT	1	
30+25	RIGHT		1
TOTAL		22	8

60221100, 60221200, 60223810 MANHOLE, TYPE A				
LOCATION		EACH		
		5' DIAMETER TYPE 1 FRAME, CLOSED LID	5' DIAMETER TYPE 3 FRAME AND GRATE	6' DIAMETER TYPE 3 FRAME AND GRATE
STATION	OFFSET	60221100	60221200	60223810
12+41	LEFT	1		
12+41	LEFT		1	
12+42	RIGHT	1		
14+00	LEFT		1	
14+62	LEFT	1		
14+88	LEFT	1		
14+88	LEFT		1	
14+88	RIGHT		1	
15+75	LEFT	1		
16+31	LEFT	1		
16+31	LEFT		1	
16+30	RIGHT		1	
17+26	LEFT	1		
17+96	LEFT	1		
18+19	LEFT	1		
18+19	LEFT		1	
19+00	LEFT	1		
19+00	LEFT		1	
20+00	LEFT	1		
20+75	LEFT	1		
20+75	LEFT			1
21+20	LEFT		1	
22+50	LEFT	1		
23+00	LEFT	1		
23+00	LEFT		1	
23+75	LEFT	1		
23+75	LEFT		1	
25+30	RIGHT	1		
26+24	LEFT		1	
26+34	LEFT		1	
26+34	RIGHT		1	
27+17	RIGHT		1	
27+97	RIGHT		1	
28+06	RIGHT	1		
28+89	RIGHT	1		
29+25	RIGHT	1		
29+50	RIGHT	1		
30+25	RIGHT	1		
TOTAL		21	16	1

REVISIONS	
NAME	DATE
IDOT	5-15-08

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 IL ROUTE 47  
 GRUNDY COUNTY

SCALE: NONE  
 DATE: 09/2007

DRAWN BY: KHH  
 CHECKED BY: FML