

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	STRUCTURE 80% FEDERAL 20% STATE X081-2A														
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1														
63200310	GUARDRAIL REMOVAL	FOOT	511	511														
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	50.0	50.0														
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4														
67100100	MOBILIZATION	L SUM	1	1														
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1														
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	136	136														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	45	45														
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425	425														
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400	400														
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,543	1,543														
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9														
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2														
78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14														
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	515	515														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11														
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	299	299														
X0324865	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	782	782														
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	172.0	172.0														
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	531	531														
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, TANGENT	EACH	3	3														
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1														
XX005496	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	EACH	1	1														
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52	52														
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2														
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2														

LEGEND:
* SPECIALTY ITEMS

▲ REVISED 9/2/08

SHEET NO. 2 OF 2

FILE NAME =	USER NAME = SJS	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...\\110149\Quantities\SUMMGTY.DGN		DRAWN -	REVISED -	SUMMARY OF QUANTITIES				721	(115BR-1)BR	PIATT	32	4
Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 28.0000' / IN. PLOT DATE = 06/17/2008 16:11:50	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 70433				
		DATE -	REVISED -									