

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007; THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JANUARY 1, 2008; AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED NEAR LAWRENCEVILLE ON BUS US-50 IN LAWRENCE COUNTY. THE PROJECT INCLUDES STRUCTURE NUMBER 051-0053.

THE WORK INCLUDED IN THIS PROJECT CONSISTS OF CONSTRUCTION OF PCC BASE COURSE WIDENING, REMOVAL OF THE EXISTING NEOPRENE JOINT SEAL EXPANSION JOINTS AND REPLACING THEM WITH PREFORMED JOINT STRIP SEAL EXPANSION JOINTS, AND A FINGER JOINT AT PIER 1, AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR WORK.

ALL EXCAVATED MATERIAL SHALL BE DISPOSED OF OFF THE RIGHT OF WAY. EXCAVATION AND DISPOSAL OF THE EXCAVATED MATERIAL WILL BE INCLUDED IN THE CONTRACT PRICE FOR PCC BASE CORSE WIDENING, 8".

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING - LINE 4 INCH CONSISTS OF:

STR#	WHITE FT	YELLOW FT
051-0053	2915	682

THE REFLECTIVE LENSE OF ALL RAISED REFLECTIVE MARKERS LOCATED BETWEEN THE START OF TAPER AND THE ABUTMENT ON EACH SIDE OF THE STRUCTURE SHALL BE REMOVED PRIOR TO STAGE I CONSTRUCTION. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL. REPLACEMENT OF THE BI-DIRECTIONAL AMBER REFLECTORS AT THE COMPLETION OF STAGE II WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR REPLACEMENT REFLECTOR.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATION AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 800-892-0123. A MINIMUM OF 96 HOURS ADVANCE NOTICE IS REQUESTED.

INDEX OF SHEETS

SHEET NO

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 BASE COURSE WIDENING
- 5 STAGE CONSTRUCTION I
- 6 STAGE CONSTRUCTION I AT PIER 1
- 7 STAGE CONSTRUCTION II
- 8-14 BRIDGE PLAN AND DETAILS 051-0053
- 15 PREFORMED JOINT STRIP SEAL
- 16 BAR SPLICER ASSEMBLY
- 17-22 FINGER PLATE DETAILS AT PIER 1

LIST OF HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-01 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 701001-01 OFF-ROAD OPERATIONS, 2L, 2W, More Than 4.5 m (15') Away
- 701006-02 OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" AWAY, SPEEDS > 45 MPH
- 701011-01 OFF-ROAD MOVING OPERATIONS, 2L 2W, DAY ONLY, FOR SPEEDS > 45 MPH
- 701321-09 LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
- 701326-02 LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING for Speeds > 45 MPH
- 701901 TRAFFIC CONTROL DEVICES
- 704001-04 TEMPORARY CONCRETE BARRIER
- 720001 SIGN PANEL MOUNTING DETAILS
- 720006-01 SIGN PANEL ERECTION DETAILS
- 780001-01 TYPICAL PAVEMENT MARKINGS
- 781001-02 TYPICAL APPLICATIONS OF RAISED REFLECTIVE PAVEMENT MARKERS

FILE NAME = c:\projects\74328b\shshtcover_74328.dgn	USER NAME = teasieyck	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEETS	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 20,0000' / IN.	CHECKED -	REVISED -	1807 D7 BRIDGE REPAIRS 2009-2			LAWRENCE	22	2		
PLOT DATE = 7/11/2008	DATE -	REVISED -	CONTRACT NO. 74328							
SCALE:	SHEET NO.	OF	SHEETS			STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	