



GENERAL NOTES

Reinforcement bars shall conform to the requirements of ASTM A 706 Gr 60. See Special Provisions.

Reinforcement bars designated (E) shall be epoxy coated.

Plan dimensions and details relative to existing plans are subject to routine variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensations for a change in scope of the work; however, the Contractor will be paid for the quantity actually furnished based upon the unit price bid for the work.

Removal of Bituminous Surface at the Expansion Joint shall be included in the contract unit price for concrete removal.

Existing reinforcement bars shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal operations shall be repaired or replaced using an approved bar splicer or anchorage system (cost included in concrete removal).

Joint openings shall be adjusted according to Article 520.04(c) of the Standard Specifications when the deck is poured at an ambient temperature other than 50 F.



SCOPE OF WORK

New strip seal at W.About., Bent 4, Bent 9 & Pier 4.
New finger plate at Pier 1.

BILL OF MATERIALS

ITEM DESCRIPTION	UNIT	QUANTITY
Concrete Removal	CU YD	11.8
Concrete Superstructure	CU YD	13.3
Reinforcement Bars, Epoxy Coated	POUND	2240
Bar Splicers	EACH	29
Preformed Joint Strip Seal	FOOT	168