# SUMMARY OF QUANTITIES

## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE: URBAN I000 100% STATE | SIGNALS Y031-IF 100% STATE | ------- |
|---|---|---|---|---|---|---|
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 956 | 956 | | |
| 80300100 | LOCATING UNDERGROUND CABLE | FOOT | 235 | | 235 | |
| 81012500 | CONDUIT IN TRENCH, 1 1/2" DIA., PVC | FOOT | 210 | | 210 | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 15 | | 15 | |
| 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 65 | | 65 | |
| 81400700 | HANDHOLE, PORTLAND CEMENT CONCRETE | EACH | 2 | | 2 | |
| 81603030 | UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE | FOOT | 250 | | 250 | |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 13 | | 13 | |
| * 89000100 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | 1 | |
| 89501250 | RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 | | 1 | |
| 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 2720 | | 2720 | |
| 89502380 | REMOVE EXISTING HANDHOLE | EACH | 2 | | 2 | |
| 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 1 | | 1 | |
| C2002636 | SHRUB, EUONYMUS ALATA COMPACTA (DWARF WINGED EUONYMUS), 3' HEIGHT, BALLED AND BURLAPPED | EACH | 12 | 12 | | |
| D2C03536 | EVERGREEN, TAXUS X MEDIA DENSIFORMIS DENSE ANGLOJAPANESE YEW), 3' WIDTH, CONTAINER | EACH | 10 | 10 | | |
| K1005481 | SHREDDED BARK MULCH 3" | SQ YD | 97 | 97 | | |
| X0301115 | LANDSCAPE EDGING | FOOT | 115 | 115 | | |
| X0321501 | WEED BARRIER FABRIC | SQ YD | 97 | 97 | | |
| X0325541 | REMOVE EXISTING LIGHTING SYSTEM | L SUM | 1 | | 1 | |
| X7800100 | PAINT PAVEMENT MARKING - RAISED MEDIAN | SQ FT | 20 | 20 | | |
| X7800200 | PAINT PAVEMENT MARKING CURB | FOOT | 232 | 232 | | |
| * X8570100 | DISCONNECT SWITCH | EACH | 1 | | 1 | |
| * XX002012 | RELOCATE SIGN, SPECIAL | EACH | 1 | 1 | | |
| * XX005944 | FLOOD LIGHT, GROUND MOUNTED, 175 WATTS, METAL HALIDE | EACH | 4 | | 4 | |

## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE: URBAN I000 100% STATE | SIGNALS Y031-IF 100% STATE | ------- |
|---|---|---|---|---|---|---|

*Specialty Items

| | | | |
|---|---|---|---|
| FILE NAME = c:\projects\ed01808\plan\pln01808a.dgn | USER NAME = conoverpj | DESIGNED - ___ | REVISED - ___ |
| | | DRAWN - ___ | REVISED - ___ |
| | PLOT SCALE = 50.0000 ' / IN. | CHECKED - ___ | REVISED - ___ |
| | PLOT DATE = 7/9/2008 | DATE - _____ | REVISED - ___ |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: _____ | SHEET NO. __ OF ___ SHEETS | STA. _____ TO STA. _____

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 592 | 65I-TS-1 | MADISON | 50 | 3A |
| | | CONTRACT NO. 76B41 | | |

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT