

STRIPING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKINGS		POLYUREA PAVEMENT MARKINGS				PAINT PAVEMENT MARKINGS			PREFORMED PLASTIC PVT MKS TYPE B LETTERS AND SYMBOLS (SQ FT)	RAISED REFL. PAVT. MKR. ONE-WAY CRYSTAL (EACH)	PRISMATIC CURB REFLECTORS		
		4" WHITE (FOOT)	8" WHITE (FOOT)	4" YELLOW (FOOT)	4" WHITE (FOOT)	8" WHITE (FOOT)	12" WHITE (FOOT)	CURB		RAISED MEDIAN			CRYSTAL (EACH)	AMBER (EACH)	
								YELLOW (FOOT)	WHITE (FOOT)	YELLOW (SQ FT)					
UNIVERSITY PARK DRIVE (EASTBOUND) STA. 201+16.18 TO STA. 206+69.03	EDGE LINE			391	477	583								22	7
	LANE LINE				337	61									
	SKIP DASH 2'-6'				39										
	SKIP DASH 16'-8'							32							
	STOP BARS								24						
	DIAGONALS								164						
	ARROWS										130				
	RAISED MEDIAN									20					
	CURB									200					
UNIVERSITY PARK DRIVE (WESTBOUND) STA. 304+07.05 TO STA. 305+60.40	EDGE LINE				123	215							22		
	LANE LINE				25										
	SKIP DASH 10'-30'				10										
	DIAGONALS								111						
IL RT 157 STA. 517+06.70 TO STA. 529+31.21	EDGE LINE	927											3		
	LANE LINE	573	229												
	SKIP DASH 2'-6'	100													
	ARROWS										78				
TOTAL		1600	229	391	1011	859	299	32	200	20	208	25	22	7	

STORM SEWER SCHEDULE

LOCATION	RCCP TYPE 1 CLASS IV 18" (FOOT)	TRENCH BACKFILL (CU YD)
	UNIVERSITY PARK DRIVE (EASTBOUND) STA. 202+56.13-24.53' RT TO STA. 202+62.32-37.94' RT	9
TOTAL	9	6

PROTECTIVE COAT SCHEDULE

LOCATION	AREA (SQ YD)
UNIVERSITY PARK DRIVE	
PORTLAND CEMENT CONCRETE PAVEMENT, 8"	1172
COMBINATION CURB AND GUTTER, B-6.06	13
COMBINATION CURB AND GUTTER, B-6.24	73
COMBINATION CURB AND GUTTER, B-6.24, VARIABLE WIDTH GUTTER FLAG	52
CONCRETE GUTTER OUTLET	37
CONCRETE MEDIAN	174
TOTAL	1521

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 1 (AC)	TEMPORARY EROSION CONTROL SEEDING (LB)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (AC)
UNIVERSITY PARK DRIVE (EASTBOUND) STA. 201+16.18 TO STA. 206+69.03	0.12	12	11	11	11	0.12
UNIVERSITY PARK DRIVE (WESTBOUND) STA. 304+07.05 TO STA. 305+60.40	0.02	2	2	2	2	0.02
IL RT 157 STA. 517+06.70 TO STA. 529+31.21	0.11	11	10	10	10	0.11
TOTAL	0.25	25	23	23	23	0.25

PAVEMENT MARKING REMOVAL

LOCATION	PAVEMENT MARKING REMOVAL		
	SOLID LINE (SQ FT)	ARROWS (SQ FT)	STOP BAR (SQ FT)
UNIVERSITY PARK DRIVE (EASTBOUND) STA. 201+16.18 TO STA. 206+38.40	298		12
UNIVERSITY PARK DRIVE (WESTBOUND) STA. 303+58.53 TO STA. 305+29.00	158		
IL RTE 157 STA. 517+06.70 TO STA. 529+31.21	457	31	
TOTAL	913	31	12