

INDEX OF SHEETS

- 1. COVER SHEET
- 2. INDEX OF SHEETS, GENERAL NOTES, STANDARDS
- 3. SUMMARY OF QUANTITIES
- 4 - 5. TRAFFIC CONTROL PLAN
- 6 - 7. BRIDGE REPAIR PLANS

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP
 - AT&T ILLINOIS
 - CHARTER COMMUNICATION
 - CITY OF SALEM
 - TRI-COUNTY ELECTRIC COOPERATIVE, INC
 - US SONET

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY •. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
4. NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING, TOPOGRAPHY, ETCETERA SHOWN IS APPROXIMATE AND WAS CREATED USING MICROFILM.
5. THREE (3) CHANGEABLE MESSAGE SIGNS SHALL BE REQUIRED ON THE PROJECT. THE MESSAGE SIGNS SHALL BE PLACED ONE WEEK BEFORE ANY LANE RESTRICTION. THE MESSAGE SIGN SHALL BE PLACED ON THE NORTHBOUND OF I 57 AND ON EACH LEG OF US 50 AS DIRECTED BY THE ENGINEER.
6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT PLUS THE INTERSECTING SIDEROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE 48" FLUORESCENT ORANGE.
7. THE CONTRACTOR SHOULD INSURE THAT, IN AND ADJACENT TO WORK AREAS, ALL LOOSE, SPALLED AND DELAMINATED CONCRETE IS REMOVED PRIOR TO REOPENING LANES TO TRAFFIC. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCIDENTAL TO "CONCRETE REMOVAL".

STANDARDS

000001-05
 701423-02
 701901
 704001-04

COMMITMENTS

NONE

FILE NAME =	USER NAME = gelsnh	DESIGNED - HG	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et\projects\0876c17\design\0876c17-sht-gannote.dgn	DRAWN - HG	REVISED - ---	57					61-3HB-1HDF	MARION	7	2	
PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---	SCALE: _____ SHEET NO. 2 OF 7 SHEETS STA. _____ TO STA. _____			CONTRACT NO. 76C17						
PLOT DATE = 7/7/2008	DATE - -----	REVISED - ---	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT									