

SCHEDULES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP734	98-00480-00-BR 03-00522-00-TL	WINNEBAGO	62	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SEGMENTAL CONCRETE BLOCK WALL		
STATION	SQ FT	REMARKS
L 425+40 TO 425+53.5	102	
LT 425+56	26	BOTH SIDES OF STEPS
L 425+58.5 TO 426+07.5	420	
L 426+10	26	BOTH SIDES OF STEPS
L 426+12.5 TO 426+147.5	291	
L 426+50	17	BOTH SIDES OF STEPS
L 426+52.5 TO 426+75.77	142	
PROJECT TOTAL	1,024	

RIFLE STRUCTURE		
STATION	EACH	REMARKS
PARK AREA EAST OF KISHWAUKEE		
168' R OF KISHWAUKEE CL (UPSTREAM)	1	SEE SHEET #21 FOR LOCATION
337' R OF KISHWAUKEE CL (UPSTREAM)	1	SEE SHEET #21 FOR LOCATION
489' R OF KISHWAUKEE CL (UPSTREAM)	1	SEE SHEET #21 FOR LOCATION
PROJECT TOTAL	3	

CONNECT TO EXISTING 8" WATERMAIN		
STATION	EACH	REMARKS
9' L 426+33	1	
PROJECT TOTAL	1	

CONCRETE MEDIAN SURFACE, (STAMPING)		
STATION	SQ FT	REMARKS
417+24.00 TO 417+79.00	361	
418+00.68 TO 419+45.00	1,264	
PROJECT TOTAL	1,625	

FIRE HYDRANT COMPLETE		
STATION	EACH	REMARKS
13' L 417+29	1	
16' L 421+65	1	
9' L 424+92	1	REQUIRES PIPE PROTECTION
PROJECT TOTAL	3	

VALVE VAULTS TO BE ABANDONED		
STATION	EACH	REMARKS
10' L 417+27	1	TO BE FILLED
12.5' L 421+03	1	TO BE FILLED
7.3' L 421+28	1	TO BE FILLED
59.5' R 421+34	1	TO BE FILLED
12' L 426+27	1	TO BE FILLED
14' L 426+65	1	TO BE FILLED
11' L 428+37	1	TO BE FILLED
PROJECT TOTAL	7	

SELECT GRANULAR BACKFILL		
STATION	CU YD	REMARKS
SANITARY SEWER		
425+04	41 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
425+76	42 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
426+00	42 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
426+43	42 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
427+24	42 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
427+36	26 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
427+88	24 (NP)	4" DIA. SAN. SERVICE - KISHWAUKEE ST
416+50	65 (NP)	6" DIA. SAN. SERVICE - KISHWAUKEE ST
416+61	51 (NP)	6" DIA. SAN. SERVICE - KISHWAUKEE ST
417+32	53 (NP)	6" DIA. SAN. SERVICE - KISHWAUKEE ST
L 417+56	80 (NP)	6" DIA. SAN. SERVICE - KISHWAUKEE ST
415+67.32 TO 417+62	226 (NP)	12" DIA. SANITARY - KISHWAUKEE STREET
418+22 TO 419+18.08	113 (NP)	12" DIA. SANITARY - KISHWAUKEE STREET
396' R 420+35 TO 383' R 420+50	21 (P)	21" DIA. SAN. SEWER - PARK AREA
3+17.28 TO 4+69.98	465 (P)	24" DIA. SAN. SEWER - LEWIS ST
4+69.98 TO 7+34.18	986 (P)	24" DIA. SAN. SEWER - LEWIS ST
7+34.18 TO 10+07.30	1054 (P)	24" DIA. SAN. SEWER - LEWIS ST
10+07.30 TO 12+54.16	688 (P)	24" DIA. SAN. SEWER - LEWIS ST
WATER MAIN		
14' L 415+76 TO 13' L 417+34	83 (NP)	12" WATER MAIN
14' L 418+34 TO 16' L 421+00	160 (NP)	12" WATER MAIN
13' L 417+29	13 (NP)	12" WATER MAIN
16' L 421+00 TO 15' L 421+96	50 (NP)	12" WATER MAIN
15' L 421+96 TO 15' L 423+96	105 (P)	12" WATER MAIN
15' L 423+96 TO 9' L 423+96	3 (NP)	12" WATER MAIN
9' L 423+96 TO 8' L 427+00	160 (NP)	12" WATER MAIN
16' L 421+65	11 (NP)	12" WATER MAIN
9' L 424+92	16 (NP)	12" WATER MAIN
8' L 427+00 TO 8' L 428+45	76 (NP)	12" WATER MAIN
8' L 428+45 TO 10' L 428+45	1 (NP)	12" WATER MAIN
10' L 428+45 TO 10' L 428+50	3 (NP)	12" WATER MAIN
COPPER WATER SERVICES (ALL)	165 (NP)	
PARTICIPATING	3,319	(P)
NON-PARTICIPATING	1,588	(NP)
PROJECT TOTAL	4,907	

SEEDING, SPECIAL		
STATION	SQ YD	REMARKS
PARK AREA EAST OF KISHWAUKEE		
L 20+30 TO 27+12.50	2,420	NEW CHANNEL - SEEDING AND LANDSCAPING
R 20+30 TO 27+12.50	2,323	NEW CHANNEL - SEEDING AND LANDSCAPING
PROJECT TOTAL	4,743	

INLETS, TYPE 700		
STATION	EACH	REMARKS
78' R 415+70	1	
R 416+03.30	1	
62.54' R 416+83.79	1	
L 417+65.46	1	
1.39' R 417+67	1	
R 417+59	1	
1.39' R 419+42.29	1	
12.16' R 419+42.29	1	
49.54' L 424+15.54	1	
8.5' L 9+00.78	1	
35.8' L 9+00.75	1	
35.48' L 424+80.30	1	
R 426+78.39	1	
PROJECT TOTAL	13	

FORM LINER TEXTURED SURFACE		
STATION	SQ YD	REMARKS
STA. 423+30	424	EAST ABUT. BOX CULVERT
EAST ABUT. PED. BRIDGE	76	
PROJECT TOTAL	500	

SANITARY SEWER REMOVAL 24"		
STATION	FOOT	REMARKS
PARK AREA EAST OF KISHWAUKEE		
194' R OF KISHWAUKEE CL (UPSTREAM)	100	SEE SHEET #21 FOR LOCATION
PROJECT TOTAL	100	

SANITARY MANHOLE, 5' DIA.		
STATION	EACH	REMARKS
3+17.28 (MH #3)	1	SAN. SEWER - LEWIS ST
7+34.18 (MH #5)	1	SAN. SEWER - LEWIS ST
PROJECT TOTAL	2	

SANITARY SEWER SERVICE 6"		
STATION	FOOT	REMARKS
416+50	58	EXTENDS TO ROW (R)
416+61	52	EXTENDS TO ROW (L)
417+15	48	EXTENDS TO ROW (L)
L 417+56	68	TIES INTO EXIST. SAN. SERVICE
PROJECT TOTAL	226	

PLUG WATER MAIN 12"		
STATION	EACH	REMARKS
14' L 415+76	1	
10' L 428+50	1	
PROJECT TOTAL	2	

CONNECT TO EXISTING WATERMAIN 4"		
STATION	EACH	REMARKS
15' L 423+96	1	
428+50	1	
PROJECT TOTAL	2	

CONNECT TO EXISTING WATERMAIN 12"		
STATION	EACH	REMARKS
14' L 415+76	1	
10' L 428+50	1	
PROJECT TOTAL	2	

SANITARY SEWER SERVICE 4"		
STATION	FOOT	REMARKS
425+04	56	EXTENDS TO ROW (L)
425+76	48	EXTENDS PAST RETAINING WALL (L)
426+00	48	EXTENDS PAST RETAINING WALL (L)
426+43	48	EXTENDS PAST RETAINING WALL (L)
427+24	48	EXTENDS TO ROW (L)
427+36	30	EXTENDS TO ROW (R)
427+88	27	EXTENDS TO ROW (R)
PROJECT TOTAL	305	

GATE VALVE AND BOX 8"		
STATION	EACH	REMARKS
426+33	1	
PROJECT TOTAL	1	

STEEL CASING PIPE AUGERED AND JACKED 20"		
STATION	FOOT	REMARKS
WATER MAIN		
13' L 417+34 TO 14' L 418+34	100	FOR 12" WATER MAIN
SANITARY SEWER		
7' R 417+62 TO 418+22	60	FOR 12" SANITARY SEWER
PROJECT TOTAL	160	

GATE VALVE WITH BOX 4"		
STATION	EACH	REMARKS
428+50	1	
PROJECT TOTAL	1	

BUTTERFLY VALVE, 12" DIA. W/ VAULT		
STATION	EACH	REMARKS
14' L 415+76	1	
9' L 423+96	1	
7' L 428+32	1	
PROJECT TOTAL	3	

WATER SERVICE PROTECTION		
STATION	FOOT	REMARKS
R 416+15	22	
R 416+33	22	
R 417+30	22	
L 425+64	22	
L 425+88	22	
L 426+70	22	
L 427+12	22	
PROJECT TOTAL	154	

1" COPPER SERVICE COMPLETE		
STATION	EACH	REMARKS
15' L 416+15	1	
14' L 416+33	1	
13' L 417+30	1	
14' L 418+65	1	
9' L 425+64	1	
9' L 425+88	1	
9' L 426+70	1	
8' L 427+12	1	
8' L 427+56	1	
PROJECT TOTAL	9	