

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1458	03-00125-01-GE	FULTON	48	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

20100500 TREE REMOVAL, ACRES

LOCATION	ACRE	REMARKS
32+00.00 TO 39+25.00 RT	0.50	
39+75.00 TO 41+00.00 RT	0.10	
45+00.00 TO 48+00.00 RT	0.40	
51+00.00 TO 56+00.00 RT	0.50	
TOTAL		1.50

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

LOCATION	CU. YD	REMARKS
50+00.00 RT	371.9	SHORT WINGWALLS
50+71.00 AR	2302.0	UNDER CULVERT
50+71.00 AR	-244.0	OVERLAP
50+16.00 LT	603.0	LONG WINGWALLS
TOTAL		3033

21101505 TOPSOIL EXCAVATION AND PLACEMENT

LOCATION	CU. YD	REMARKS
31+80.00 TO 45+00.00	682.5	NOMINAL THICKNESS, 3"
45+00.00 TO 60+00.00	1479.6	NOMINAL THICKNESS, 3"
60+00.00 TO 71+00.00	516.6	NOMINAL THICKNESS, 3"
TOTAL		2679

25000200 SEEDING, CLASS 2

LOCATION	ACRE	REMARKS
31+80.45 TO 45+00.00	1.70	
45+00.00 TO 46+50.00	0.20	
56+50.00 TO 60+00.00	0.70	
60+00.00 TO 70+97.16	1.30	
TOTAL		4.00

25000300 SEEDING, CLASS 3

LOCATION	ACRE	REMARKS
46+50.00 TO 56+50.00	2.75	
TOTAL		2.75

25000400 NITROGEN FERTILIZER NUTRIENT

LOCATION	POUND	REMARKS
31+80.00 TO 45+00.00	152.1	
45+00.00 TO 60+00.00	330.3	
60+00.00 TO 71+00.00	113.4	
TOTAL		596

25000500 PHOSPHORUS FERTILIZER NUTRIENT

LOCATION	POUND	REMARKS
31+80.00 TO 45+00.00	152.1	
45+00.00 TO 60+00.00	330.3	
60+00.00 TO 71+00.00	113.4	
TOTAL		596

25000600 POTASSIUM FERTILIZER NUTRIENT

LOCATION	POUND	REMARKS
31+80.00 TO 45+00.00	152.1	
45+00.00 TO 60+00.00	330.3	
60+00.00 TO 71+00.00	113.4	
TOTAL		596

25100115 MULCH, METHOD 2

LOCATION	ACRE	REMARKS
31+80.00 TO 45+00.00	1.54	
45+00.00 TO 60+00.00	3.42	
60+00.00 TO 71+00.00	1.20	
TOTAL		6.25

25100630 EROSION CONTROL BLANKET

LOCATION	SQ. YD	REMARKS
42+25.00 TO 45+00.00 LT	397.2	DITCH
42+50.00 TO 45+00.00 RT	361.1	DITCH
56+50.00 TO 59+00.00 LT	361.1	DITCH
57+00.00 TO 59+50.00 RT	390.6	DITCH
60+12.00 TO 62+00.00 RT	271.6	DITCH
TOTAL		1782

28000250 TEMPORARY EROSION CONTROL SEEDING

LOCATION	POUND	REMARKS
31+80.00 TO 45+00.00	169.2	
45+00.00 TO 60+00.00	366.8	
60+00.00 TO 71+00.00	126.0	
TOTAL		662

28000300 TEMPORARY DITCH CHECKS

LOCATION	EACH	REMARKS
31+80.00 TO 45+00.00 LT	21	
31+80.00 TO 45+00.00 RT	16	
45+00.00 TO 60+00.00 LT	48	
45+00.00 TO 60+00.00 RT	39	
60+00.00 TO 71+00.00 LT	7	
60+00.00 TO 71+00.00 RT	6	
TOTAL		137

28000400 PERMETER EROSION BARRIER

LOCATION	FOOT	REMARKS
31+80.45 TO 34+50.00	269.6	
36+50.00 TO 38+00.00	150.0	
TOTAL		420

28000500 INLET AND PIPE PROTECTION

LOCATION	EACH	REMARKS
39+58.00 LT	1	END SECTIONS 24"
41+56.00 LT	1	END SECTIONS 12"
41+92.00 RT	1	END SECTIONS 12"
60+13.00 LT	1	
60+10.00 RT	1	END SECTIONS 12"
63+06.00 LT	1	
TOTAL		6

28100705 STONE DUMPED RIPRAP, CLASS A3

LOCATION	SQ. YD	REMARKS
39+50.00 TO 40+50.00 LT	144.4	DITCH LINING
38+50.00 TO 40+00.00 RT	216.7	DITCH LINING
45+00.00 TO 51+00.00 LT	866.7	DITCH LINING
45+00.00 TO 50+00.00 RT	722.2	DITCH LINING
51+25.00 TO 56+50.00 LT	758.3	DITCH LINING
50+00.00 TO 57+00.00 RT	1011.1	DITCH LINING
TOTAL		3719

28100707 STONE DUMPED RIPRAP, CLASS A4

LOCATION	SQ. YD	REMARKS
50+00.00 RT	80.0	CULVERT EXIT
51+17.00 LT	58.7	CULVERT ENTRANCE
TOTAL		139

35100200 AGGREGATE BASE COURSE TYPE A

LOCATION	CU. YD	REMARKS
31+80.00 TO 45+00.00	1289.0	
45+00.00 TO 60+00.00	1882.4	
60+00.00 TO 71+00.00	1513.7	
TOTAL		4685

35101800 AGGREGATE BASE COURSE TYPE B, 6"

LOCATION	SQ. YD	REMARKS
41+29.00 TO 41+59.00 LT	15.6	MAILBOX TURNOUT
41+75.00 LT	215.0	ENTRANCE
42+19.00 RT	155.0	ENTRANCE
59+80.00 RT	271.0	ENTRANCE
TOTAL		657

40200500 AGGREGATE SURFACE COURSE TYPE A, 6"

LOCATION	SQ. YD	REMARKS
31+80.45 TO 45+00.00	3518.8	
45+00.00 TO 60+00.00	4000.0	
60+00.00 TO 70+97.16	2925.8	
TOTAL		10445

REVISIONS	
NAME	DATE

SCHEDULE OF QUANTITIES
SHEET 1 OF 2

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY