

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	80% FED 20% STATE		80% FED 20% STATE		80% FED 20% STATE		100% CITY		50% STATE 50% CITY	
				L 24		L 24		L 20					
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)		
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071					
				CONSTRUCTION CODE TYPE									
				I000-2A RURAL	I000-2A RURAL	I000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN					
M4075350	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 350MM	SQ M	6,984	6,984									
M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	23,137	19,770	1,981	1,386							
M4080300	AGGREGATE (PRIME COAT)	M TON	12	11		1							
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	1,936	1,642	159	135							
M4200200	PORTLAND CEMENT CONCRETE PAVEMENT 200MM	SQ M	2,252		2,252								
M4205100	PAVEMENT FABRIC	SQ M	2,252		2,252								
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	1,191	333	858								
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	4,087	1,758	2,329								
M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	3,293.5		1,493.5							1,800.0	
M4245000	TEMPORARY SIDEWALK	SQ M	200		200								
M4248000	DETECTABLE WARNINGS	SQ M	39.7		39.7								
M4400715	HOT-MIX ASPHALT SURFACE REMOVAL, 15MM	SQ M	87,188	77,092	6,684	3,412							
M4400725	HOT-MIX ASPHALT SURFACE REMOVAL, 25MM	SQ M	3,400		3,400								
M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SQ M	212		212								
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	10,944	8,933	2,011								
M4402000	PAVEMENT REMOVAL	SQ M	11,736	5,539	6,197								
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	8,669	5,716	2,550	403							
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	2,496		2,496								
M4402050	SIDEWALK REMOVAL	SQ M	3,767		1,927				1,840				
M4405000	PAVED DITCH REMOVAL	METER	996	996									
M4420300	PAVEMENT PATCHING, TYPE I 300MM	SQ M	322	322									
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SQ M	241	241									
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	31,381	30,124	21	1,236							
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	22,554	21,877	10	667							
M5010521	REMOVE EXISTING CULVERTS	METER	180	100	71	9							
M5010522	PIPE CULVERT REMOVAL	METER	2,137	1,954	58	125							
M5030300	CLASS MS CONCRETE	CU M	12.0		12.0								
M5030350	CONCRETE STRUCTURES	CU M	4.9	4.9									
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	260	260									
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	880	880									
M5401002	PRECAST CONCRETE BOX CULVERT 600MM x 450MM	METER	15.1	15.1									
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	15.6	15.6									
M5401010	PRECAST CONCRETE BOX CULVERT 900MM x 600MM	METER	5.7	5.7									
M5401020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M	METER	19.8	19.8									
M5401060	PRECAST CONCRETE BOX CULVERT 1.8M x 1.2M	METER	25.2	25.2									
M5402020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M (M273)	METER	30.6	30.6									
M5402035	PRECAST CONCRETE BOX CULVERT 1.5M x 0.9M (M273)	METER	9.0	9.0									
M5403220	EXPANSION BOLTS M20	EACH	206	206									
M5421210	PIPE CULVERTS, TYPE 1 RCCP 375MM	METER	126.5	110.5		16.0							
M5421215	PIPE CULVERTS, TYPE 1 RCCP 450MM	METER	66.0	53.5		12.5							
M5421225	PIPE CULVERTS, TYPE 1 RCCP 600MM	METER	118.5	118.5									
M5421235	PIPE CULVERTS, TYPE 1 RCCP 750MM	METER	32.5	32.5									
M5421240	PIPE CULVERTS, TYPE 1 RCCP 900MM	METER	55.5	55.5									
M5421260	PIPE CULVERTS, TYPE 1 RCCP 1500MM	METER	17.5	17.5									
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	EACH	1		1								
M542C216	REINFORCED CONCRETE PIPE TEE, 375MM PIPE WITH 300MM RISER	EACH	1	1									
M542C220	REINFORCED CONCRETE PIPE TEE, 450MM PIPE WITH 300MM RISER	EACH	2		2								
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	8		8								
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	5		5								
M542C244	REINFORCED CONCRETE PIPE TEE, 900MM PIPE WITH 300MM RISER	EACH	7		7								
M542C248	REINFORCED CONCRETE PIPE TEE, 1050MM PIPE WITH 300MM RISER	EACH	3		3								
M542C328	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 375MM RISER	EACH	1	1									
M542C336	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 375MM RISER	EACH	1	1									
M542E012	END SECTIONS 300MM	EACH	1	1									

* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE APRIL 18, 2008 CHECKED BY RGH</p>

Rev. 9-8-08