

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE				
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	50% STATE 50% CITY
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071
				1000-2A RURAL	1000-2A RURAL	1000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN
M4075350	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 350MM	SQ M	6,984	6,984				
M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	23,137	19,770	1,981	1,386		
M4080300	AGGREGATE (PRIME COAT)	M TON	12	11		1		
* M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	1,936	1,642	159	135		
M4200200	PORTLAND CEMENT CONCRETE PAVEMENT 200MM	SQ M	2,252		2,252			
M4205100	PAVEMENT FABRIC	SQ M	2,252		2,252			
M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	1,191	333	858			
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	4,087	1,758	2,329			
* M4240100	PORTLAND CEMENT CONCRETE SIDEWALK 100MM	SQ M	3,293.5		1,493.5			1,800.0
* M4245000	TEMPORARY SIDEWALK	SQ M	200		200			
* M4248000	DETECTABLE WARNINGS	SQ M	39.7		39.7			
* M4400715	HOT-MIX ASPHALT SURFACE REMOVAL, 15MM	SQ M	87,188	77,092	6,684	3,412		
* M4400725	HOT-MIX ASPHALT SURFACE REMOVAL, 25MM	SQ M	3,400		3,400			
* M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SQ M	212		212			
* M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	10,944	8,933	2,011			
M4402000	PAVEMENT REMOVAL	SQ M	11,736	5,539	6,197			
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	8,669	5,716	2,550	403		
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	2,496		2,496			
M4402050	SIDEWALK REMOVAL	SQ M	3,767		1,927		1,840	
* M4405000	PAVED DITCH REMOVAL	METER	996	996				
M4420300	PAVEMENT PATCHING, TYPE I 300MM	SQ M	322	322				
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SQ M	241	241				
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	31,381	30,124	21	1,236		
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	15,354	14,924	5	425		
* M5010521	REMOVE EXISTING CULVERTS	METER	180	100	71	9		
* M5010522	PIPE CULVERT REMOVAL	METER	2,137	1,954	58	125		
M5030300	CLASS MS CONCRETE	CU M	12.0		12.0			
M5030350	CONCRETE STRUCTURES	CU M	4.9	4.9				
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	260	260				
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	880	880				
M5401002	PRECAST CONCRETE BOX CULVERT 600MM x 450MM	METER	15.1	15.1				
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	15.6	15.6				
M5401010	PRECAST CONCRETE BOX CULVERT 900MM x 600MM	METER	5.7	5.7				
M5401020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M	METER	19.8	19.8				
M5401060	PRECAST CONCRETE BOX CULVERT 1.8M x 1.2M	METER	25.2	25.2				
M5402020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M (M273)	METER	30.6	30.6				
M5402035	PRECAST CONCRETE BOX CULVERT 1.5M x 0.9M (M273)	METER	9.0	9.0				
M5403220	EXPANSION BOLTS M20	EACH	206	206				
M5421210	PIPE CULVERTS, TYPE 1 RCCP 375MM	METER	126.5	110.5		16.0		
M5421215	PIPE CULVERTS, TYPE 1 RCCP 450MM	METER	66.0	53.5		12.5		
M5421225	PIPE CULVERTS, TYPE 1 RCCP 600MM	METER	118.5	118.5				
M5421235	PIPE CULVERTS, TYPE 1 RCCP 750MM	METER	32.5	32.5				
M5421240	PIPE CULVERTS, TYPE 1 RCCP 900MM	METER	55.5	55.5				
M5421260	PIPE CULVERTS, TYPE 1 RCCP 1500MM	METER	17.5	17.5				
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	EACH	1		1			
M542C216	REINFORCED CONCRETE PIPE TEE, 375MM PIPE WITH 300MM RISER	EACH	1	1				
M542C220	REINFORCED CONCRETE PIPE TEE, 450MM PIPE WITH 300MM RISER	EACH	2		2			
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	8		8			
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	5		5			
M542C244	REINFORCED CONCRETE PIPE TEE, 900MM PIPE WITH 300MM RISER	EACH	7		7			
M542C248	REINFORCED CONCRETE PIPE TEE, 1050MM PIPE WITH 300MM RISER	EACH	3		3			
M542C328	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 375MM RISER	EACH	1	1				
M542C336	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 375MM RISER	EACH	1	1				
M542E012	END SECTIONS 300MM	EACH	1	1				

* SEE SPECIAL PROVISIONS

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE APRIL 18, 2008 CHECKED BY RGH</p>

PLOT DATE = 4/18/2008
FILE NAME = H:\4428\78084_sumq_v8.dgn

H. M. & G. NO. 4420