

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE							
				L24		L24		L20		100% CITY	
				80% FED	20% STATE	80% FED	20% STATE	80% FED	20% STATE	SFTY-1B	URBAN
				F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)		F.A.P. 781 (IL. RTE. 33)	
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000		2+756.900 TO 4+475.071		15+545.000 TO 16+016.000		2+756.900 TO 4+475.071	
				I000-2A RURAL		I000-2A RURAL		I000-2A URBAN		SFTY-1B URBAN	
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	1430	1330				100			
** M7800205	PAINT PAVEMENT MARKING LINE-100 MM	METER	33577	32091		426		1060			
** M7800215	PAINT PAVEMENT MARKING LINE-150 MM	METER	106.8			106.8					
** M7800240	PAINT PAVEMENT MARKING LINE-600 MM	METER	15.6			15.6					
* MX032188	CLASS SI CONCRETE, SPECIAL	CU M	15.0			15.0					
* MX032196	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ M	25.9	25.9							
* MX032200	ENGINEERED BARRIER	SQ M	457			457					
* MX032509	GRADING AND SHAPING SPECIAL	SQ M	9815			9815					
* M2112500	TOPSOIL EXCAVATION AND PLACEMENT	CU M	24190	23434.0		9.7		741.7			
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	3.2	3.2							
MX540110	PRECAST CONCRETE BOX CULVERT 1.5M x 0.6M	METER	64.4			64.4					
MX033731	PRECAST CONCRETE BOX CULVERT 900MM x 450MM	METER	15.2	15.2							
MX033735	PRECAST CONCRETE BOX CULVERT 3.0M x 0.9M	METER	43.2	43.2							
MX033732	PRECAST CONCRETE BOX CULVERT 3.0M x 1.65M	METER	10.9	10.9							
MX033736	PRECAST CONCRETE BOX CULVERT 750MM x 450MM (M273)	METER	51.0	36.6		14.4					
MX033737	PRECAST CONCRETE BOX CULVERT 900MM x 300MM (M273)	METER	29.7	29.7							
MX033734	PRECAST CONCRETE BOX CULVERT 1.8M x 0.6M (M273)	METER	15.3	15.3							
* MZ034730	MODULAR RETAINING WALL SYSTEM	SQ M	97.1			97.1					
* Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1							
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4							
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	15	13		2					
** A2001010	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30		5		5			
** A2006410	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30		5		5			
** D2002280	EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	15			15					
** A2001210	TREE, ACER SACCHARINUM (SILVER MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	35	30		5					
** A2006910	TREE, QUERCUS PALUSTRIS (PIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	40	30		5		5			
o Z0076400	TRAINEES	HR	1000	1000							
MX030199	TEMPORARY PAVEMENT	SQ M	3451	3451							
MX030203	TEMPORARY PAVEMENT REMOVAL	SQ M	3451	3451							
MX033748	TEMPORARY EMBANKMENT PLACEMENT AND REMOVAL	CU M	853	853							

\* SEE SPECIAL PROVISIONS  
 \*\* Specialty Items  
 o Y080

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

**SUMMARY OF QUANTITIES**

SCALE \_\_\_\_\_ DRAWN BY KOJ  
 DATE APRIL 18, 2008 CHECKED BY RGH

PLOT DATE = 4/18/2008  
 FILE NAME = H:\4420\70804\_sumq\_v8.dgn

H. M. & G. NO. 4420