

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S.B.L.	06-00032-00-SW	MOULTRIE	24	4
F.A.				
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

CONTRACT #9556I

SIDEWALK ENHANCEMENT PROJECT					
SECTION 06-00032-00-SW					
SUMMARY OF QUANTITIES					
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	H22	070
				SFTY-1B	SFTY-1B
				PARTICIPATING	NON-PARTICIPATING
20800150	TRENCH BACKFILL	CU YD	4	4	-
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.9	0.9	-
28000510	INLET FILTERS	EACH	12	12	-
35100040	STOCK PILING SALVAGED AGGREGATE	CU YD	27	27	-
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	30	30	-
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	50		50
42001300	PROTECTIVE COAT	SQ YD	2,500	2,500	-
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	198	198	-
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	9,509	9,509	-
42400500	PORTLAND CEMENT CONCRETE SIDEWALK SPECIAL	SQ FT	7,834	7,834	-
42400800	DETECTABLE WARNINGS	SQ FT	432	432	-
44000100	PAVEMENT REMOVAL	SQ YD	1,695	1,695	-
*550A2310	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 10"	FOOT	17	17	-
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1	-
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	-
60260100	INLETS TO BE ADJUSTED	EACH	8	8	-
60261200	INLETS TO BE ADJUSTED WITH NEW TYPE 10 FRAME AND GRATE	EACH	2	2	-
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1	-
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	288	-	288
67100100	MOBILIZATION	L SUM	1	1	-
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	-
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	-
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	-
*80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	-
*81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	1,880	1,880	-
*81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	1,065	1,065	-
*81400100	HANDHOLE	EACH	3	3	-
*81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	3,659	3,659	-
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,940	1,940	-
*82500510	LIGHTING CONTROLLER TYPE CB-RCS 60 AMP-240 VOLT	EACH	1	1	-
*89502205	MODIFY EXISTING CONTROLLER (SPECIAL)	EACH	1	1	-
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	12	12	-
*XX005043	ORNAMENTAL SIGN-POSTS	EACH	14	14	-
*XX001136	LIGHT POLE (SPECIAL)	EACH	27	27	-
*X0321766	LIGHT POLE (DECORATIVE ORNAMENTAL)	EACH	7	7	-

\*Specialty Items

Revised 9-15-08

**M**  
L  
U  
E  
E  
N  
G  
I  
N  
E  
E  
R  
I  
N  
G

MILANO & GRUNLOH ENGINEERS, LLC  
 84 WEST WASHINGTON  
 P.O. BOX 897  
 EFFINGHAM, ILLINOIS 62401  
 PHONE: (217) 347-7262  
 (800) 677-2714  
 FAX #: (217) 342-3433

SUMMARY OF QUANTITIES  
SIDEWALK ENHANCEMENT  
CITY OF SULLIVAN

File name: S:\DWG\06\06244\dwg\Quantities.dwg  
 Plot date: 05/23/08 at 13:55