

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION STATION TO STATION	NUMBER OF BARRIER (FOR INFORMATION ONLY)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	COMMENTS
	EACH	FOOT	FOOT	
FAP RT. 322(US 51)				
STAGE I				
799+37 TO 800+37	8	100.0		12: 1 TAPER
800+37 TO 800+50	1	12.5		20: 1 TAPER
800+50 TO 802+63	17	212.5		TANGENT
802+63 TO 802+75	1	12.5		20: 1 TAPER
801+62 TO 803+37	5	62.5		12: 1 TAPER
STAGE II				
799+60 TO 800+48	7		87.5	12: 1 TAPER
800+48 TO 800+61	1		12.5	20: 1 TAPER
800+61 TO 802+61	16		200.0	TANGENT
801+98 TO 802+73	1		12.5	20: 1 TAPER
802+73 TO 804+10	11	50.0	87.5	12: 1 TAPER
TOTALS		450	400	

FILE NAME = c:\projects\1902984\1902984ms.dgn	USER NAME = shepardgd	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TEMPORARY CONCRETE BARRIER SCHEDULE	F.A.P. RTE. FAP 322	SECTION 12-1, BR	COUNTY UNION	TOTAL SHEETS 48	SHEET NO. 12
PLOT SCALE = 50,0000' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---	SCALE: -----	SHEET NO. 12 OF 48 SHEETS	STA. ----- TO STA. -----	FED. ROAD DIST. NO. _____	ILLINOIS FED. AID PROJECT	CONTRACT NO. 98886	
PLOT DATE = 6/18/2008	DATE - -----	REVISED - ---	REVISED - ---							