

LANDSCAPE SCHEDULE

LOCATION			21101505			25000210	25000314	25000400	25000600	2500750	25100630	X2501800	X2503110
			TOPSOIL EXCAVATION	TOPSOIL PLACEMENT, 4"	TOPSOIL PLACEMENT, 6"	SEEDING, CLASS 2A	SEEDING, CLASS 4B	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	EROSION CONTROL BLANKET	SEEDING, CLASS 4 (MODIFIED)	MOWING (SPECIAL)
ROAD	START STRCT	END STRCT	CU YD	CU YD	SQ YD	ACRE	ACRE	POUND	POUND	ACRE	SQ YD	ACRE	ACRE
IL 171	START PROJ	016-0488	196.7	0	98	0.00	0.00	0	0	0.37	590	0.12	
IL 171	016-0488	016-0486	338.7	0	169	0.00	0.00	0	0	0.63	1016	0.21	
IL 171	016-0486	016-1510	221.0	0	111	0.00	0.00	0	0	0.41	663	0.14	0.41
IL 171	016-1510	016-0483	93.9	0	47	0.00	0.00	0	0	0.17	282	0.06	0.42
IL 171	016-2455	016-1005	133.2	0	67	0.00	0.00	0	0	0.25	400	0.08	
RIVER LOCATION 1			0.0	0	33	0.00	0.04	0	0	0.12		0.00	
RIVER LOCATION 2			0.0	0	115	0.00	0.14	0	0	0.43		0.00	
IL 171	016-1005	016-1000	124.2	41	0	0.08	0.00	7	7	0.23	373	0.00	
IL 171	016-1000	END	184.8	61	0	0.11	0.00	10	10	0.34	554	0.00	
IL 171	016-1006	016-1001	0.0	0	0	0.00	0.00	0	0	0.00	0	0.00	
IL 171	016-0483	016-2455	105.1	35	0	0.07	0.00	6	6	0.20	315	0.00	5.66
IL 171	016-1001	END	288.1	95	0	0.18	0.00	16	16	0.54	864	0.00	
RAMP E	016-1026	016-1512	863.6	201	1091	0.38	0.15	34	34	5.19	8371	1.20	4.63
RAMP E	016-1512	END PROJ	384.7	0	513	0.00	0.00	0	0	1.91	3076	0.64	1.29
RAMP F	016-0486	END	0.0	0	0	0.00	0.00	0	0	0.00	0	0.00	0.63

TOTAL	2,935	433	2,244	1.00	0.50	74	74	11.00	16,505	2.50	13.25		
-------	-------	-----	-------	------	------	----	----	-------	--------	------	-------	--	--

*TOPSOIL EXCAVATION AND PLACEMENT WILL BE PAID FOR AS "21101505 - TOPSOIL EXCAVATION AND PLACEMENT" WITH A TOTAL OF 2935 CU YD

REMOVAL SCHEDULE

LOCATION			44000100	44000165	44000500	44004250	X6430210
			PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	COMBINATION CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	REMOVE AND REINSTALL IMPACT ATTENUATORS
ROAD	START STRCT	END STRCT	SQ YD	SQ YD	FOOT	SQ YD	EACH
IL 171	START PROJ	016-0488	0	780	0	0	0
IL 171	016-0488	016-0486	0	1912	0	0	0
IL 171	016-0486	016-1510	0	1297	0	0	0
IL 171	016-1510	016-0483	0	2458	0	0	0
IL 171	016-2455	016-1005	0	0	0	0	0
IL 171	016-1005	016-1000	0	0	0	0	0
IL 171	016-1000	END	0	0	640	0	0
RAMP E	016-1026	016-1512	0	0	0	728	0
RAMP E	016-1512	END PROJ	0	0	0	1812	1
RAMP F	016-0486	END	2020	171	0	0	0

TOTAL	2020	6619	640	2539	1		
-------	------	------	-----	------	---	--	--

PAVEMENT SCHEDULE

LOCATION			30300112	35501327	40600982	40603240	40603595	42001420	44000100	44000165	44000500	44004250	48101202	48203048	X4060110	Z0005216
			AGGREGATE SUBGRADE IMPR 12"	HOT-MIX ASPHALT BASE COURSE 10 3/4"	HMA SURFACE REMOVAL - BUTT JOINT	POLY HMA BINDER COURSE, IL-19.0, N90	POLY HMA SURFACE COURSE, MIX "F", N90	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	PAVEMENT REMOVAL	HMA SURFACE REMOVAL, 4"	COMB CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	AGGREGATE SHOULDERS, TYPE B	HMA SHOULDERS, 12 3/4"	BITUMINOUS MATERIAL (PRIME COAT)	HMA STABILIZATION 6" AT STEEL PLATE BEAM GUARDRAIL
ROAD	START STRCT	END STRCT	SQ YD	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	POUND	SQ YD
IL 171	START PROJ	016-0488		0	120	232	180	60	0	780	0	0	39		92	350
IL 171	016-0488	016-0486		0	0	250	195	122	0	1912	0	0	17		99	125
IL 171	016-0486	016-1510		0	0	170	132	65	0	1297	0	0	15		73	133
IL 171	016-1510	016-0483		0	0	307	239	51	0	2458	0	0	32		152	133
IL 171	016-2457	016-1005		0	0	208	162	0	0	0	0	0	51		83	433
IL 171	016-1005	016-1000		0	0	295	230	0	0	0	0	0	64		117	567
IL 171	016-1000	END		0	0	209	163	0	0	0	640	0	45		83	417
RAMP E	016-1026	016-1512	5012	690.46	0	0	0	0	0	0	728	19	890		55	221
RAMP E	016-1512	END PROJ		1513.83	27	0	0	0	0	0	1812	58	1662		71	400
RAMP F	016-0486	END		0	37	104	81	41	2020	171	0	0	14		41	100

TOTAL	5012	2204	183	1775	1380	339	2020	6619	640	2539	355	2553	866	2880
-------	------	------	-----	------	------	-----	------	------	-----	------	-----	------	-----	------

EROSION CONTROL SCHEDULE

LOCATION			20101000	28000250	28000315	28000400	28000510	28001100	28100105
			TEMPORARY FENCE	TEMPORARY EROSION CONTROL SEEDING	AGGREGATE DITCH CHECKS	PERIMETER EROSION BARRIER	INLET FILTERS	TEMPORARY EROSION CONTROL BLANKET	STONE RIPRAP, CLASS A3
ROAD	START STRCT	END STRCT	FOOT	POUND	TON	FOOT	EACH	SQ YD	SQ YD
IL 171	START PROJ	016-0488	329	73		286	1	872	17
IL 171	016-0488	016-0486	285	64	44	504	1	1540	0
IL 171	016-0486	016-1510	335	26		142	0	290	0
IL 171	016-1510	016-0483	346	42		215	1	630	17
IL 171	016-2455	016-1005	979	0		0	2	0	0
IL 171	016-1005	016-1000	60	56		616	2	1044	17
IL 171	016-1000	END	240	43		328	0	866	0
IL 171	016-1006	016-1001		53		285	0	618	0
IL 171	016-0483	016-2455		0		594	0	0	0
IL 171	016-1001	END		39		545	0	1440	0
RAMP E	016-1026	016-1512	119	61		327	0	1972	0
RAMP E	016-1512	END PROJ		43		519	0	2118	0
RAMP F	016-0486	END		0		0	0	0	0

TOTAL	2693	501	44	4,361	7	11,390	51
-------	------	-----	----	-------	---	--------	----

BRIDGE APPROACH SCHEDULE

LOCATION	Z0004552	54215547	55100500	60100945	60500060	60900240	60900315	60900515	X0322936
	APPROACH SLAB REMOVAL	METAL END SECTION 12"	STORM SEWER REMOVAL 12" (FOR APPROACH)	PIPE DRAIN 12"	REMOVING INLETS	TYPE C INLET BOX, STANDARD 609006	TYPE D INLET BOX, STANDARD 609006	CONCRETE THRUST BLOCKS (FOR APPROACH)	REMOVE EXISTING FLARED END SECTION
STRUCTURE	SQ YD	EACH	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
SN 016-1000	369	0	0	0	0	0	0	0	0
SN 016-1001	0	0	0	0	0	0	0	0	0
SN 016-1005	0	0	0	0	0	0	0	0	0
SN 016-2455	112	2	108	108	2	1	1	2	2
SN 016-2457	0	0	0	0	0	0	0	0	0
SN 016-0483	82	2	0	65	1	1	1	2	0
SN 016-1026	0	0	0	0	0	0	0	0	0
SN 016-0486	405	2	0	125		2		2	
SN 016-0488	320	0	0	0	0	0	0	0	0

TOTAL	1288	6	108	298	3	4	2	6	2
-------	------	---	-----	-----	---	---	---	---	---

TREE SCHEDULE

SCIENTIFIC NAME	COMMON NAME	SIZE	TOTAL	1	2	3	4	5	6	7	8	9	10
AESCLUS FLAVEA	YELLOW SWEET BUCKEYE	2" CAL/B&B	11								11		
CAALPA SPECIOSA	NORTHERN CATALPA	2" CAL/B&B	6.00		6.00								
CELTIS OCCIDENTALIS	COMMON HACKBERRY	2" CAL/B&B	4.00		4.00								
GYMNOCLADUS DIOICUS	KENTUCKY COFFEE TREE	2" CAL/B&B	10.00								10		
QUERCUS BICOLOR	SWAMP WHITE OAK	2" CAL/B&B	10.00	5.00							5		
QUERCUS IMBRICARIA	SHINGLE OAK	2" CAL/B&B	8.00								8		
QUERCUS MACROCARPA	BUR OAK	2" CAL/B&B	10.00								10		

TREE REMOVAL SCHEDULE

LOCATION			20100110	20100210
			TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
ROAD	STA	OFFSET	(UNIT)	(UNIT)
171 SB	21+52.58	81.6 LT	15	
171 SB	21+52.58	77.0 LT	15	
171 SB	21+75.56	79.2 LT	15	
171 SB	106+21.49	71.4 LT	15	
171 SB	107+92.98	70.0 LT	15	
RAMP E	212+05.23	46.8 RT	15	
ADDITIONAL CONTINGENCY PER IDOT			1250	1000

TOTAL	1340	1000
-------	------	------

FILE NAME =	DESIGNED - AAA	REVISED -
...\\General\160J16-sh-t-SCH-01.dgn	DRAWN - TMB	REVISED -
USER NAME = tblank	CHECKED - JMM	REVISED -
PLOT DATE = 8/7/2014	DATE - 6/23/2014	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-038B-R	COOK	821	28
CONTRACT NO. 60J16			ILLINOIS FED. AID PROJECT	