

## TEMPORARY AND PROPOSED PAVEMENT MARKING SCHEDULE

LOCATION			70300100	70301000	78005100	78005110				78005130		78005140	78005150	78005180	78100200	78300100	78300200	X7030030
			SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	EPOXY PAVT MARKING - LETTERS & SYMBOLS	EPOXY PAVT MARKING - LINE 4"				EPOXY PAVT MARKING - LINE 6"		EPOXY PAVT MARKING - LINE 8"	EPOXY PAVT MARKING - LINE 12"	EPOXY PAVEMENT MARKING - LINE 24"	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH
Road	Start STA	End STA	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(SQ FT)	(EACH)	(FOOT)
SB IL171	10+00.00	39+95.06	0	0	73	2984	1897	1160	143	276	40	572	0	0	59	0	0	0
SB IL171	44+33.80	89+10.76	0	0	0	4450	2803	1483	168	0	0	744	0	0	76	0	0	0
RAMP F	29+30.00	31+97.00	0	0	0	277	269	0	0	0	0	1387	79	0	0	0	0	0
RAMP G	22+65.20	23+62.00	0	0	0	100	97	0	0	0	0	366	53	0	0	0	0	0
RAMP K	16+65.00	27+61.00	0	0	0	0	0	0	0	0	0	608	88	0	0	0	0	0
MOT																		
Road	Stage																	
IL 171	Prestage		500	260	0			5671		0	0	0	0	0	0	1924	0	3292
IL 171	Stage 1A		2500	279	185			26675		0	1342	1142	1142	20	56	4863	196	0
IL 171	Stage 1B		500	244	67			6453		0	280	602	720	40	13	720	12	0
IL 171	Stage 1C		500	3135	39			7888		0	295	0	0	0	8	4251	88	0
SUBTOTAL			4000	3918	73	7811	5066	2643	311	276	1957	5421	1964	60	212	11758	296	3292
TOTAL			4000	3918	364		62,518				2233	5421	1964	60	212	11758	296	3292

## PROPOSED PAVEMENT MARKING SCHEDULE

LOCATION			78000100	78000200			78000400	78000500	78000600	78000650
			THERMOPLASTIC PAVEMENT MARKING - LETTERS AND	THERMOPLASTIC PAVEMENT			THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"
ROAD	START STA	END STA	SQ FT	YELLOW LINE	WHITE LINE	WHITE 10' DASH 30" SKIP	FOOT	FOOT	FOOT	FOOT
SB IL 171	8+00.00	10+00.00	73	104	0	26	301	140	54	64
SB IL 171	89+10.76	119+44.97	0	4698	2575	1175	0	1538	305	0
RAMP E	197+06.62	212+63.41	0	0	0	0	0	0	0	0
RAMP E	218+05.70	226+60.00	0	0	0	0	0	0	0	0
TOTAL			73	4802	2575	1200	301	1678	359	64

## PLUGS SCHEDULE

SCIENTIFIC NAME	COMMON NAME	SIZE	TOTAL	WETLAND # 5	WETLAND # 6	PLANTING DEPTH @ NORMAL WATER LEVEL (NWL)
CALAMAGROSTIS CANADENSIS	BLUE JOINT GRASS	PLUG	1	0.75	0.25	0" (@ nwl)
CAREX LACUSTRIS	COMMON LAKE SEDGE	PLUG	0.75	0.50	0.25	0-3" below nwl
CAREX STRICTA	COMMON TUSsock SEDGE	PLUG	0.75	0.50	0.25	0" (@ nwl)
CAREX VULPINOIDEA	BROWN FOX SEDGE	PLUG	0.75	0.50	0.25	0" (@ nwl)
GLYCERIA TRIATA	FOWL MANNA GRASS	PLUG	0.75	0.50	0.25	0" (@ nwl)
JUNCUS TORREYI	TORRREY'S RUSH	PLUG	0.75	0.50	0.25	3-6" below nwl
SAGITTARIA LATIFOLIA	COMMON ARROW-HEAD	PLUG	0.75	0.50	0.25	3-6" below nwl
SCIRPUS ATROVIRENS	DARK GREEN BULRUSH	PLUG	0.75	0.50	0.25	0-3" below nwl
SCIRPUS VALIDUS CREBER	GREAT BULRUSH	PLUG	0.75	0.50	0.25	3-6" below nwl
SPARTINA PECTINATA	PRAIRIE CORD GRASS	PLUG	1.00	0.75	0.25	0-3" below nwl

## EARTHWORK SCHEDULE

LOCATION	20200100	EXCAVATION VOLUME TO BE USED IN EMBANKMENT, ADJUSTED FOR 15% SHRINKAGE		EMBANKMENT VOLUME	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) VOLUME
	EARTH EXCAVATION	(CU YD)	(CU YD)		
	(CU YD)	(CU YD)	(CU YD)		
CROSSOVERS	174	148	1736	-1,588	
SN 016-1000	332	282	565	-283	
SN 016-1001	263	224	447	-223	
SN 016-1005					
SN 016-2455	120	102	160	-58	
SN 016-2457					
SN 016-0483	257	218	411	-193	
SN 016-1026					
SN 016-0486	232	197	347	-150	
SN 016-0488	135	115	202	-87	
RAMP E	3,709	3153	5,147	-1,994	
TOTAL		5,222	4,439	9,015	-4,576

Pay Item 20400800 - Furnished Excavation = 4576 CU YD