SIGN DETAIL

1:76



Panel Style: GuideSign_D3-1.ssi
M.U.T.C.D.: 2009 Edition

SIGN NUMBER	SB–PM–31, STA 52+38 LT	
WIDTH x HGHT.	3'–0" x 1'–6"	
BORDER WIDTH	0.5"	
CORNER RADIUS	1.5"	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective–AP
	COLOR:	Green
LEGEND/BORDER	TYPE:	Reflective–AP
	COLOR:	White/White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: GuideSign_D3–1.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

																																				LENGTH	SERIES/SIZE
D	e	s	P	l	a	i	n	e	s																												C 2000
5.3	8.1	10.5	16.2	19.1	20.2	22.8	24.1	26.7	29																											25.5	4/3
R	i	v	e	r																																	C 2000
12.8	15.6	16.6	19.3	21.9																																10.4	4/3

LIN ENGINEERING, LTD. Consulting Engineers Westmont, Illinois	USER NAME = Plotted by Lin21	DESIGNED - RC	REVISED -
		DRAWN - RC	REVISED -
	PLOT SCALE = 6.8382 ' / in.	CHECKED - ST	REVISED -
	PLOT DATE = 8/4/2014	DATE - 6/23/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL ROUTE 171
SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 6 OF 19 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-038B-R	COOK	821	169
		CONTRACT NO. 60J16		
		ILLINOIS FED. AID PROJECT		