

SIGN SCHEDULE					72000100	72000200	72000300	72400100	72400200	7240310	7240320	7240330	72700100	72800100	73000100	73400100	73600100	73700100	73700200	73700300
					SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 3	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B	REMOVE SIGN PANEL - TYPE 1	REMOVE SIGN PANEL - TYPE 2	REMOVE SIGN PANEL - TYPE 3	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	CONCRETE FOUNDATIONS	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	REMOVE GROUND MOUNTED SIGN SUPPORT	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	REMOVE CONCRETE FOUNDATION - OVERHEAD
SIGN NAME	STATION	OFFSET	ALIGNMENT	LEGEND/DESCRIPTION	SQ FT	SQ FT	SQ FT	EACH	EACH	SQ FT	SQ FT	SQ FT	POUND	FOOT	FOOT	CU YD	EACH	EACH	EACH	EACH
SB-TS-21	80+29	LT	IL 171	D3-1	7.50			1						16						
SB-PM-20	81+38	LT	IL 171	R2-1		12.00					12.00									
SB-WP-19	81+53	LT	IL 171	R2-1		12.00		1							16					
SB-PM-18	84+32	LT	IL 171	M3-3	2.00					2.00										
SB-PM-18	84+32	LT	IL 171	M1-I100		12.00					12.00									
SB-TS-17	92+95	RT	IL 171	R11-1	5.00															
SB-TS-63	92+95	RT	IL 171	R11-1	5.00															
SB-TS-17/63	92+95	RT	IL 171	R11-1				1						16						
SB-PM-16	94+34	LT	IL 171	W4-1R		16.00					16.00				16					
SB-PM-15	97+35	LT	IL 171	R2-1		12.00					12.00									
SB-PM-14	103+29	LT	IL 171	I1-I100	8.00					8.00										
SB-PM-13	106+22	LT	IL 171	D3-1	6.75					6.75										
SB-WP-12	111+10	RT	IL 171	R2-1		12.00		1							16					
SB-PM-11	111+21	LT	IL 171	R2-1		12.00					12.00									
SB-TS-61	111+54	LT	IL 171	R5-1a	8.75															
SB-TS-10	111+54	RT	IL 171	R2-1		12.00														
SB-TS-10/61	111+54		IL 171	R2-1/R5-1a					1					16.5						
SB-TS-09	111+99		IL 171	W16-I100	9.00			1						16						
SB-WP-08	112+77	LT	IL 171	E5-1			30.00		1						16					
	114+25	LT	IL 171	GUIDE													1			4
	114+25	LT	IL 171	GUIDE																
	114+25	LT	IL 171	GUIDE																
SB-TR-07	114+60	LT	IL 171	GUIDE			43.75													
SB-TR-05	114+60	LT	IL 171	GUIDE			143.75													
SB-TR-06	114+60	LT	IL 171	GUIDE			115.00													
NB-WP-62	119+54	LT	IL 171	R3-I100	4.00															
SB-WP-04	119+54	LT	IL 171	R4-7		12.00														
SB-WP-62/04	119+54		IL 171	R4-7/R3-I100					1						16					
SB-PM-03	121+03	LT	IL 171	GUIDE		17.50					19.25									
SB-TS-02	121+96	LT	IL 171	M3-3	2.00															
SB-TS-02	121+96	LT	IL 171	M1-I100		12.00														
SB-TS-02	121+96	LT	IL 171	M1-I100/M3-3					1					16						
SB-PM-01	123+44		IL 171	R2-1		12.00					12									
SB-GM-66	209+76	LT	RAMP E	GUIDE			110.25				110.25	2023.60				4.18		1		2
SB-GM-67	209+76	RT	RAMP E	GUIDE			110.25				110.25	2023.60				4.18		1		2
SB-WP-68	210+78	LT	RAMP E	W12-1	9.00			1							16					

TOTAL	259.06	439.25	987.00	5	21	118.13	202.75	363.50	6156.20	225.00	304.00	12.54	2	3	6	8
ROUNDED TOTAL	260	440	987	5	21	119	203	364	6157	225	304	12.6	2	3	6	8



USER NAME = Plotted by LinZi	DESIGNED - RC	REVISED -
	DRAWN - RC	REVISED -
PLOT SCALE = 6.8382' / in.	CHECKED - ST	REVISED -
PLOT DATE = 8/4/2014	DATE - 6/23/2014	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 171  
SIGNING DETAILS**

SCALE: N.T.S. SHEET NO. 19 OF 19 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372/373	2013-038B-R	COOK	821	182
CONTRACT NO. 60J16				
ILLINOIS FED. AID PROJECT				