BEAM 5N

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK. S. ABUT.	103+93.22	13.46	633.32	633.32
℄ BRG. S. ABUT.	103+95.00	13.43	633.32	633.32
A	104+04.92	13.29	633.35	633.34
B	104+14.83	13.17	633.37	633.36
C	104+24.75	13.06	633.39	633.38
℄ BRG. PIER 1	104+32.15	12.99	633.40	633.40
D	104+42.07	12.91	633.42	633.45
E	104+51.99	12.86	633.43	633.49
F	104+61.91	12.81	633.44	633.54
G	104+71.82	12.79	633.45	633.57
H	104+81.74	12.78	633.45	633.58
I	104+91.66	12.79	633.46	633.57
J	105+01.58	12.82	633.46	633.55
K	105+11.50	12.86	633.46	633.51
L	105+21.42	12.93	633.45	633.47
℄ BRG. PIER 2	105+29.85	12.99	633.44	633.44
M	105+39.77	13.09	633.43	633.43
N	105+49.69	13.20	633.42	633.41
O	105+59.60	13.32	633.41	633.40
℄ BRG. N. ABUT.	105+67.00	13.43	633.40	633.40
BK. N. ABUT.	105+68.78	13.46	633.39	633.39

BEAM 6N

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK. S. ABUT.	103+93.34	20.88	633.47	633.47
℄ BRG. S. ABUT.	103+95.11	20.85	633.47	633.47
A	104+05.02	20.71	633.50	633.49
B	104+14.92	20.58	633.52	633.51
C	104+24.82	20.48	633.54	633.53
℄ BRG. PIER 1	104+32.21	20.41	633.55	633.55
D	104+42.12	20.33	633.57	633.60
E	104+52.02	20.27	633.58	633.65
F	104+61.93	20.23	633.59	633.69
G	104+71.84	20.21	633.60	633.72
H	104+81.74	20.20	633.60	633.73
I	104+91.65	20.21	633.61	633.73
J	105+01.56	20.24	633.61	633.70
K	105+11.46	20.28	633.60	633.66
L	105+21.37	20.34	633.60	633.62
℄ BRG. PIER 2	105+29.79	20.41	633.59	633.59
M	105+39.69	20.50	633.58	633.58
N	105+49.60	20.61	633.57	633.56
O	105+59.50	20.74	633.56	633.55
℄ BRG. N. ABUT.	105+66.89	20.85	633.54	633.54
BK. N. ABUT.	105+68.66	20.88	633.54	633.54

benesch
engineers · scientists · planners
Alfred Benesch & Company
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450 Job No. 10093

FILE NAME = 0161000.60J16_011_slabelevs_3.dgn	USER NAME = jsurber	DESIGNED - JOB	REVISED -
		CHECKED - DJM	REVISED -
	PLOT SCALE =	DRAWN - FMS	REVISED -
	PLOT DATE = 12/20/2012	CHECKED - RMM	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TOP OF SLAB ELEVATIONS (3 OF 3)
STRUCTURE NO. 016-1000/1001

SHEET NO. SA11 OF SA40 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
372	2013-038B-R	COOK	821	259
		CONTRACT NO. 60J16		
		ILLINOIS FED. AID PROJECT		

7/14/2014 9:19:00 AM X:\10000S\10093\Eng_Docs_Phase_II\SN_016_1000_1001_1st_Ave_over_47th_St\Final\0161000_60J16_011_slabelevs_3.dgn