

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN () WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = tblank	DESIGNED -	REVISED - R. MIRS 09-15-97		ARTERIAL ROAD	F.A.P.	SECTION	COUNTY	TOTAL SHE
\D160J16-sht-D1-tc-22.dgn		DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS		• 201	13-038B-R	соок	821 80
	PLOT SCALE =	CHECKED -	REVISED -T. RAMMACHER 02-02-99	DEPARTMENT OF TRANSPORTATION	INFORMATION SIGN	TC		CONTRACT	
	PLOT DATE = 6/23/2014	DATE -	REVISED - C. JUCIUS 01-31-07	i	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED ROAD DIST NO		AID PROJECT	