

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005 100% STATE					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	20					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	25	25					
25200110	SODDING, SALT TOLERANT	SO YD	25	25					
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	24848	24848					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	56	56					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1450	1450					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	153	153					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	732	732					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3304	3304					
42001300	PROTECTIVE COAT	SO YD	743	743					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	2922	2922					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0005 100% STATE					
42400800	DETECTABLE WARNINGS	SO FT	160	160					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	26630	26630					
44000600	SIDEWALK REMOVAL	SO FT	2922	2922					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	10847	10847					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	70	70					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	70	70					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	182	182					
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	2021	2021					
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	325	325					
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	140	140					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	727	727					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8					
60406000	FRAMES AND LIDS, TYPE I, OPEN LID	EACH	2	2					
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	2	2					

FILE NAME =	USER NAME = perry/roal	DESIGNED -	REVISED -
C:\perry\roal\perry\roal\0246302-000311-111-plans.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**147TH STREET (JUSTAMERE ROAD TO IL. ROUTE 50 /CICERO AVENUE)
SUMMARY OF QUANTITIES**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1602	74-R5-2	COOK	32	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60M02	

SCALE: SHEET NO. OF SHEETS STA. TO STA.