

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	28	28			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	77	77			
25200110	SODDING, SALT TOLERANT	SO YD	77	77			
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	28	28			
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	21672	21672			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	1325	1325			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	429	429			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2700	2700			
42001300	PROTECTIVE COAT	SO YD	642	642			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	4621	4621			
42400800	DETECTABLE WARNINGS	SO FT	448	448			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	32106	32106			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	28	28			
44000600	SIDEWALK REMOVAL	SO FT	4537	4537			
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	654	654			
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	172	172			
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	571	571			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10			
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	2	2			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	30	30			
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			

* Specialty Items

13

FILE NAME =	USER NAME = Torlofm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67100100		DRAWN -	REVISED -			3518	0405.2-RS	COOK	24	3
PLOT SCALE = 1000000' / 1"		CHECKED -	REVISED -			CONTRACT NO. 60M23				
PLOT DATE = 7/11/2014		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT	