



**PROJECT BEGINS
STA 00+00**

PAVEMENT MARKINGS

- (A) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (WHITE) (10' DASH, 30' SKIP)
- (B) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW) (10' DASH, 30' SKIP)
- (C) THERMOPLASTIC PAVEMENT MARKING - LINE 4" (YELLOW)
- (D) THERMOPLASTIC PAVEMENT MARKING - LINE 6" (WHITE)
- (E) THERMOPLASTIC PAVEMENT MARKING - LINE 8" (WHITE)
- (F) THERMOPLASTIC PAVEMENT MARKING - LINE 8" (YELLOW)
- (G) THERMOPLASTIC PAVEMENT MARKING - LINE 12" (WHITE)
- (H) THERMOPLASTIC PAVEMENT MARKING - LINE 12" (YELLOW)
- (J) THERMOPLASTIC PAVEMENT MARKING - LINE 24" (WHITE)
- (K) THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

ROADWORK LEGEND

- (1) PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL - 2 1/4"
 PROPOSED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 - 1 1/2"
 PROPOSED POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 - 3/4"
- (2) PROPOSED SIDEWALK REMOVAL
 PROPOSED PCC SIDEWALK, 5"
 PROPOSED DETECTABLE WARNINGS
 PROPOSED REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
 • SEE GENERAL NOTES

FILE NAME =	USER NAME = tarigfm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY AND PAVEMENT MARKING PLAN KIRCHOFF RD. (NEW WILKE RD. TO CENTRAL AVE.)	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw\work\p\idot\tarigfm\d0241225\0109011-sht-plan.dgn	DRAWN -	REVISED -	3518			0405.2-RS	COOK	24	7	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 60M23							
PLOT DATE = 7/11/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
						SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.