

SIGN SCHEDULE

STATION	OFFSET	SIGN	METAL POST				
			SIGN PANEL - TYPE 1 SQ FT (72000100)	SIGN PANEL - TYPE 2 SQ FT (72000200)	NUMBER OF POLES	TYPE A	TYPE B
						TOTAL LENGTH (FT) (72900100)	TOTAL LENGTH (FT) (72900200)
15+75.00	39 LT	R3-5R	7.5		1.0	12.5	
16+73.00	42 LT	W2-3	9.0		2.0	27.4	
16+73.00	42 LT	W16-8P	1.1			-	
16+74.00	30 RT	R2-1	7.5		2.0		28.0
16+74.00	30 RT	W14-3		9.9			-
18+01.00	27 LT	R2-1	7.5		2.0		28.0
18+01.00	27 LT	W14-3		9.9			-
22+72.00	24 RT	R2-1	7.5		1.0		13.0
24+26.00	23 LT	I1-I104	2.5		1.0		13.0
24+26.00	23 LT	I2-I105	2.8				-
24+37.00	24 RT	I1-I104	2.5		1.0	11.0	
26+30.00	23 LT	W11-10	9.0		2.0	27.4	
27+48.00	23 RT	W2-1	9.0		2.0	27.4	
27+48.00	23 RT	W16-8P	1.3			-	
28+08.00	22 LT	W3-5	9.0		2.0	27.4	
36+29.00	23 LT	R2-1	7.5		1.0		13.0
38+31.00	23 LT	M3-4	2.0		1.0		13.0
38+31.00	23 LT	M1-I100	4.0				-
38+35.00	24 RT	W14-3		9.9	2.0		28.0
39+89.00	48 RT	R1-1	9.0		2.0	25.0	
39+89.00	48 RT	W4-4P	2.0			-	
39+91.00	51 RT	M1-I100	4.0		1.0	12.8	
39+91.00	51 RT	M6-5	2.2			-	
39+99.00	41 LT	M1-I100	4.0		1.0		13.3
39+99.00	41 LT	M6-5	2.2			-	
40+01.50	37 LT	R1-1	9.0		2.00	25.0	
40+01.50	37 LT	W4-4P	2.0			-	
41+56.00	24 RT	M3-2	2.0		1.0		13.0
41+56.00	24 RT	M1-I100	4.0				-
42+26.00	24 RT	I1-I107a	5.0		1.0		13.8
42+26.00	24 RT	I1-I107b	2.5				-
44+27.00	24 RT	R2-1	7.5		1.0		13.0
44+66.00	24 LT	W14-3		9.9	2.0		28.0
47+92.00	24 LT	W2-1	9.0		2.0	27.4	
47+92.00	24 LT	W16-8P	1.4			-	
77+29.00	46 RT	R1-1	6.3		1.0		12.5
79+25.00	23 RT	W2-2	9.0		2.0	27.4	
79+25.00	23 RT	W16-8P	1.1			-	
84+17.00	24 LT	S4-I105	5.0		1.0	12.0	
86+75.00	24 LT	R2-1	7.5		1.0		13.0
88+73.00	24 LT	M3-4	2.0		1.0		13.0
88+73.00	24 LT	M1-I100	4.0				-
90+56.00	30 RT	W14-3		9.9	2.0		28.0
90+94.00	24 LT	I1-I107a	5.0		1.0		13.8
90+94.00	24 LT	I1-I107b	2.5				-
91+44.00	44 RT	R1-1	6.3		1.0		12.5
91+58.00	30 LT	W1-7	8.0		1.0		12.0
93+78.00	23 RT	M3-2	2.0		1.0		13.0
93+78.00	23 RT	M1-I100	4.0				-
97+90.00	25 RT	R2-1	7.5		1.0		13.0

SIGN SCHEDULE

STATION	OFFSET	SIGN	METAL POST				
			SIGN PANEL - TYPE 1 SQ FT (72000100)	SIGN PANEL - TYPE 2 SQ FT (72000200)	NUMBER OF POLES	TYPE A	TYPE B
						TOTAL LENGTH (FT) (72900100)	TOTAL LENGTH (FT) (72900200)
98+52.00	22 LT	W2-2	9.0		2.0	27.4	
98+52.00	24 LT	W16-8P	1.1			-	
115+40.00	24 LT	W14-3		9.9	2.0		28.0
115+93.00	24 RT	W2-2	9.0		2.0	27.4	
115+93.00	24 RT	W16-8P	1.6			-	
122+59.00	34 LT	R1-1	6.3		1.0		12.5
129+90.00	25 LT	W2-2	9.0		2.0	27.4	
129+90.00	25 LT	W16-8P	1.6			-	
135+12.00	27 RT	W2-1	9.0			-	
135+12.00	27 RT	W16-8P	1.8			-	
138+38.00	25 LT	R2-1	7.5		1.0		13.0
139+97.00	31.0 RT	W1-2	9.0		2.0	27.4	
140+48.00	24 LT	M3-4	2.0		1.0		13.0
140+48.00	24 LT	M1-I100	4.0				-
142+66.00	41 LT	R1-1	9.0			-	
142+66.00	41 LT	W4-4P	2.0			-	
142+99.00	37 RT	R1-1	9.0			-	
142+99.00	37 RT	W4-4P	2.0			-	
145+05.00	25 RT	W3-5a	9.0		2.0	27.4	
147+17.00	24 RT	M3-2	2.0		1.0		13.0
147+17.00	24 RT	M1-I100	4.0				-
150+46.00	24 LT	R2-1	7.5		1.0		13.0
150+47.00	24 RT	R2-1	7.5		1.0		13.0
152+28.00	22 LT	W2-1	9.0			-	
152+28.00	22 LT	W16-8P	1.8			-	
158+26.00	27 RT	W14-3		9.9	2.0		28.0
159+67.00	30 LT	W1-2	9.0		2.0	27.4	
164+84.00	32 LT	W6-3	9.0		2.0	27.4	
164+92.00	34 RT	M2-1	3.1		2.0		29.8
164+92.00	34 RT	M1-I100	9.0				-
164+92.00	34 RT	W16-8P	2.0				-
167+09.00	33 LT	W4-2	9.0		2.0	27.4	
168+39.00	35 LT	S4-I105	5.0		1.0	12.0	
TOTAL			405	69		494	511

REMOVE AND RELOCATE SIGN SCHEDULE

STATION	OFFSET	SIGN	REMOVE SIGN PANEL ASSEMBLY - TYPE A (72400100)	RELOCATE SIGN PANEL ASSEMBLY - TYPE A (72400500)
102+04.00	24 RT	EAST DUNDEE FIRE DISTRICT	1	1
122+13.00	33 LT	D3-1 (WOODCREEK ROAD)	1	1
128+67.00	24 RT	BC FPD 29W061	1	1
129+28.00	24 RT	BC FPD 29W059	1	1
146+65.00	24 RT	BC FPD 28W947	1	1
152+33.00	24 RT	BC FPD 28W803	1	1
156+54.00	23 RT	BC FPD 28W735	1	1
TOTAL			49	6

FILE NAME = \$FILEL\$

USER NAME = \$USER\$	DESIGNED - MTM	REVISED -
	DRAWN - MTM	REVISED -
PLOT SCALE = \$SCALE\$	CHECKED - BA	REVISED -
PLOT DATE = \$DATE\$	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE 68 (DUNDEE ROAD) - PRAIRIE LAKE ROAD TO IL 62
SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343	631 RS-3	KANE/COOK	73	12
CONTRACT NO. 60T04			ILLINOIS FED. AID PROJECT	