

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005	0021		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	405	405			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7.6	7.6			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7.6	7.6			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7.6	7.6			
25200110	SODDING, SALT TOLERANT	SO YD	405	405			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	22	22			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	347	347			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	9523	9523			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1136	1136			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3	3			
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	22,622	22,622			
42001300	PROTECTIVE COAT	SO YD	361	361			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	20	20			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1900	1900			
42400800	DETECTABLE WARNINGS	SO FT	210	210			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005	0021		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	230,827	230,827			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	42	42			
44000600	SIDEWALK REMOVAL	SO FT	1837	1837			
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SO YD	500	500			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	6000	6000			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	1925	1925			
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	2120	2120			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	479	479			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15			
60403700	LIDS, TYPE 1, OPEN LID	EACH	15	15			
60403800	LIDS, TYPE 1, CLOSED LID	EACH	50	50			
60404940	FRAMES AND GRATES, TYPE 23	EACH	5	5			
60404950	FRAMES AND GRATES, TYPE 24	EACH	6	6			
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	25	25			
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1			

FILE NAME :	USER NAME : <i>hardmaster</i>	DESIGNED -	REVISED -
<i>c:\aw_sart\awh\hardmaster\0313769\025002-01-plot.dwg</i>		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REV. 9-4-14  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	(I&I)RS-3	LAKE	60	3
CONTRACT NO. 60V03			FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT	

\*Specialty Items