


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	
				ROADWAY 0004 URBAN	S.N. 016-1510 0011 URBAN	S.N. 016-1512 0011 URBAN	SAFETY 0021 URBAN	SIGN STRUCTURES 0040 URBAN	DRAINAGE 0044 URBAN	
60200305	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2							2
60218300	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2							2
60235610	INLETS, TYPE A, TYPE 2 FRAME AND GRATE	EACH	16							16
60500040	REMOVING MANHOLES	EACH	2							2
60500050	REMOVING CATCH BASINS	EACH	2							2
60500060	REMOVING INLETS	EACH	16							16
60900515	CONCRETE THRUST BLOCKS	EACH	8							8
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	8							8
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	437.5				437.5			
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1				1			
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	5				5			
63200310	GUARDRAIL REMOVAL	FOOT	1274				1274			
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	522	522						
63700805	CONCRETE BARRIER TRANSITION	FOOT	90	90						

• SPECIALTY ITEM

FILE NAME =	DESIGNED - AAA	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P.	SECTION	COUNTY	TOTAL	SHEET
USER NAME = tbiernk	DRAWN - TMB	REVISED -							373	10701-608 & 611HS-8	COOK	177	8
PLOT DATE = 6/27/2014	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET 5 OF 10 SHEETS STA. TO STA.				CONTRACT NO. 60W77		ILLINOIS FED. AID PROJECT		