

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				ROADWAY 0004 URBAN	S.N. 016-1510 0011 URBAN	S.N. 016-1512 0011 URBAN	SAFETY 0021 URBAN	SIGN STRUCTURES 0040 URBAN	DRAINAGE 0044 URBAN
81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	20				20		
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	280				280		
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"X6"X4"	EACH	2				2		
81200270	CONDUIT EMBEDDED IN STRUCTURE, 4" DIA., PVC	FOOT	20				20		
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"X12"X6"	EACH	7				7		
81300800	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18"X12"X6"	EACH	2				2		
81400200	HEAVY-DUTY HANDHOLE	EACH	6				6		
81603081	UNIT DUCT, 600V, 3-1C NO. 2. 1/C NO. 4 GROUND. (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	325				325		
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1730				1730		
81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	2500				2500		
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	10				10		
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	20				20		
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	7				7		
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2				2		

• SPECIALTY ITEM