

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE		
				ROADWAY 0005		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	26	26		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	269	269		
25200110	SODDING, SALT TOLERANT	SO YD	269	269		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	10,448	18,448		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	43	43		
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1411	1411		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	403	403		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	78	78		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3156	3156		
42001300	PROTECTIVE COAT	SO YD	1141	1141		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	7829	7829		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE		
				ROADWAY 0005		
42400800	DETECTABLE WARNINGS	SO FT	1198	1198		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	2536	2536		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	25,640	25,640		
44000600	SIDEWALK REMOVAL	SO FT	7471	7471		
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	463	463		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	150	150		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	120	120		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	120	120		
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	15	15		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		

\* SPECIALTY ITEMS

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
DESIGNED BY :	DRAWN :	CHECKED :	REVISED :
PLOT SCALE :	CHECKED :	DATE :	REVISED :
PLOT DATE :			

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

DEMPSTER ST. (McCORMICK BLVD. TO RIDGE AVE.)  
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3727	2013-050-RS	COOK	22	3
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60X01	

REV. 9-4-14

Rev.