## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE: 100% STATE | ROADWAY 0005 |
|---|---|---|---|---|---|
| 20201200 | REMOVAL AND DISPOSAL OF UNSUITABLE | CU YD | 26 | 26 | |
| | MATERIAL | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 269 | 269 | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 269 | 269 | |
| 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | POUND | 18,448 | 18,448 | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND | TON | 43 | 43 | |
| | FLANGEWAYS | | | | |
| 40600827 | POLYMERIZED LEVELING BINDER (MACHINE | TON | 1411 | 1411 | |
| | METHOD), IL-4.75, N50 | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT | SQ YD | 403 | 403 | |
| | JOINT | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER | TON | 78 | 78 | |
| | PATCHES | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX | TON | 3156 | 3156 | |
| | "D", N70 | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 1141 | 1141 | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 7829 | 7829 | |

* SPECIALTY ITEMS

## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE: 100% STATE | ROADWAY 0005 |
|---|---|---|---|---|---|
| 42400800 | DETECTABLE WARNINGS | SQ FT | 1198 | 1198 | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 3" | SQ YD | 2536 | 2536 | |
| 44000161 | HOT-MIX ASPHALT SURFACE REMOVAL, 3" | SQ YD | 25,640 | 25,640 | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 7471 | 7471 | |
| 44002212 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3" | SQ YD | 463 | 463 | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 150 | 150 | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 120 | 120 | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 120 | 120 | |
| 60300105 | FRAMES AND GRATES TO BE ADJUSTED | EACH | 15 | 15 | |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 5 | 5 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, | L SUM | 1 | 1 | |
| | STANDARD 701501 | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, | L SUM | 1 | 1 | |
| | STANDARD 701606 | | | | |

Rev.

| | | | |
|---|---|---|---|
| FILE NAME = c:\pw_work\pwidot\tarlqf\d0352106\D46613-sht-plan.dgn | USER NAME = Tarlqfm | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000 ' / in. | CHECKED - | REVISED - |
| | PLOT DATE = 7/10/2014 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**DEMPSTER ST. (McCORMICK BLVD. TO RIDGE AVE.)**
**SUMMARY OF QUANTITIES**

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 3727 | 2013-050-RS | COOK | 22 | 3 |
| | | CONTRACT NO. 60X01 | | |

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT