

GENERAL NOTES

1. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT 800-892-0123 OR 811 FOR FIELD LOCATIONS, BURIED ELECTRIC LINES, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
2. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES, TO HAVE THE LOCATION OF EXISTING UTILITIES STAKED AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO EXCAVATION. THE CONTRACTOR SHALL NOTIFY THE VILLAGE OF BOLINGBROOK AND THE VILLAGE OF ROMEOVILLE, AT LEAST SEVENTY-TWO (72) HOURS PRIOR TO EXCAVATION.
3. THERE ARE EXISTING IDOT LIGHTING FACILITIES AND IDOT SURVEILLANCE FACILITIES LOCATED WITHIN THE LIMITS OF THIS CONTRACT THAT MUST REMAIN FUNCTIONING AT ALL TIMES. THESE FACILITIES ARE NOT INCLUDED IN THE J.U.L.I.E. SYSTEM. THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER A MINIMUM OF 10 DAYS PRIOR TO START OF WORK FOR THESE FACILITIES TO BE FIELD LOCATED.
4. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
5. WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED EACH LOCATION.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE LOCATIONS OF ALL UTILITIES FROM THE UTILITY COMPANIES AND BY FIELD INSPECTIONS.
7. ALL EXCAVATED MATERIAL ALONG WITH UNSUITABLE EXCAVATED MATERIAL SHALL BE STOCKPILED ON-SITE. NO MATERIAL IS TO BE REMOVED FROM THE JOBSITE. STOCKPILE LOCATIONS ARE TO BE DETERMINED BY THE ENGINEER.
8. THE CONTRACTOR SHALL TAKE CARE IN REMOVING OR EXCAVATING NEAR ALL EXISTING ITEMS WHICH WILL REMAIN. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
9. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, AS REQUIRED, PRIOR TO COMMENCING WITH CONSTRUCTION.
10. POLLUTION CONTROL: THE CONTRACTOR SHALL BE REQUIRED TO COMPLY WITH STATE REGULATIONS REGARDING AIR, WATER AND NOISE POLLUTION.
11. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE CONSTRUCTION OF THIS PROJECT.
12. THE CONTRACTOR SHALL CONTACT THE IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4171 72 HOURS PRIOR TO TRANSPLANTING TO LAYOUT LOCATIONS WITHIN THE INTERCHANGE NOT SUBJECT TO FUTURE IMPACTS FROM CONSTRUCTION.
13. THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.
14. NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET.
15. DURING CONSTRUCTION OPERATIONS, WHENEVER LOOSE MATERIAL IS DEPOSITED IN THE FLOW LINE OF GUTTERS, DRAINAGE STRUCTURES, DITCHES, ETC., SUCH THAT THE NATURAL FLOW LINE OF WATER IS OBSTRUCTED, THE LOOSE MATERIAL SHALL BE REMOVED AT THE CLOSE OF EACH WORKING DAY. AT THE CONCLUSION OF THE CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS. THE CONTRACTORS FAILURE TO PROVIDE THE ABOVE WILL PRECLUDE ANY POSSIBLE ADDED COMPENSATION REQUESTED DUE TO DELAYS OR UNSUITABLE MATERIAL CREATED AS A RESULT THERE OF.

FILE NAME = D:\82753\int-03-General Notes.dgn

Rev. 9-4-14

	USER NAME = moastro	DESIGNED PAW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN PAW	REVISED -	55			(99-1HB-11A)	WILL	33	3	
	PLOT SCALE = 1:2,000.00	CHECKED PJO	REVISED -			CONTRACT NO. 60Y53			ILLINOIS FED. AID PROJECT	
	PLOT DATE = 7/31/2014	DATE 7/31/2014	REVISED -			SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	