

EROSION CONTROL ITEMS

From			To			LOCATION	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	STABILIZED CONSTRUCTION ENTRANCE	STONE RIPRAP, CL A5	FILTER FABRIC
STA	OFFSET	LT/RT	STA	OFFSET	LT/RT								
6001+25	55	RT	6001+29	22	LT	RAMP B	77						
6001+29	22	LT	6001+73	75	LT	RAMP B	72						
6001+73	75	LT	6004+16	59	LT	RAMP B	418						
6004+16	59	LT	6004+28	31	RT	RAMP B	92						
6004+33	66	LT	6006+75	24	RT	RAMP B	99						
Topsoil Stockpile Perimeter						RAMP B	330	787	16				
6001+32	-	LT/RT	6006+75	-	LT/RT	RAMP B		6683	138				
6002+71	44	RT	-	-	-	RAMP B				25			
6003+92	49	RT	-	-	-	RAMP B				25			
6005+13	50	RT	-	-	-	RAMP B				25			
6006+32	37	RT	-	-	-	RAMP B				25			
6006+50	-	RT	-	-	-	RAMP B					200		
6001+39	60	RT	-	-	-	RAMP B						33	33
9001+22	75	LT	9005+56	47	LT	RAMP D	317						
9005+56	47	LT	9005+94	24	RT	RAMP D	82						
Topsoil Stockpile Perimeter						RAMP D	302	662	14				
9001+53	-	LT/RT	9006+19	-	LT/RT	RAMP D		5022	104				
9002+03	58	LT	-	-	-	RAMP D				25			
9001+74	9	LT	-	-	-	RAMP D				25			
9002+58	41	RT	-	-	-	RAMP D				25			
9004+04	40	RT	-	-	-	RAMP D				25			
9005+58	31	RT	-	-	-	RAMP D				25			
9005+82	11	RT	-	-	-	RAMP D				25			
9006+15	-	RT	-	-	-	RAMP D					200		
9001+43	54	RT	-	-	-	RAMP D						33	33
9005+90	0	-	-	-	-	RAMP D						28	28
<b>TOTALS</b>							<b>1789</b>	<b>13154</b>	<b>272</b>	<b>250</b>	<b>400</b>	<b>94</b>	<b>94</b>

FILE NAME : D:\60Y53-shr-03-Miscellaneous Schedule.dwg

USER NAME = llugo	DESIGNED LL	REVISED -
	DRAWN KES	REVISED -
PLOT SCALE = 1:2.000001	CHECKED PJO	REVISED -
PLOT DATE = 7/16/2014	DATE 7/16/2014	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES  
EROSION CONTROL ITEMS

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(99-1HB-1)A	WILL	33	9
CONTRACT NO. 60Y53			ILLINOIS FED. AID PROJECT	