

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	41931	41931			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	94	94			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2379	2379			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	292	292			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5406	5406			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	61828	61828			
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	2800	2800			
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	1400	1400			
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SQ YD	2300	2300			
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1714	1714			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	21916	21916			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	510	510			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	73345	73345			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1122	1122			
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	130	130			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	420	420			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	89	89			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	25694	25694			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510			
	* SPECIALTY ITEMS						

12

FILE NAME :	USER NAME : porgroot	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 72 (US 20 - I-90) SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10/16/2014	10/16/2014	DRAWN -	REVISED -				341	109RS-4	KANE	29	3
PLOT SCALE : 1/4" = 1'	1/4" = 1'	CHECKED -	REVISED -				CONTRACT NO. 60Y62				
PLOT DATE : 7/16/2014	7/16/2014	DATE -	REVISED -				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				