

SCHEDULE OF QUANTITIES

I-72 EASTBOUND CLASS A 15" PATCHES										
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200630 TYPE II 15.0" (SQ YD)	44213200 SAW CUTS (FT)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	URBAN	1933+14.07	181.232	EB	DL	6	12	8.0	60.0	8.0
SUB-TOTALS =								8.0	60.0	8.0
I-72 WESTBOUND CLASS A 15" PATCHES										
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200630 TYPE II 15.0" (SQ YD)	44213200 SAW CUTS (FT)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	URBAN	1810+75.03	178.914	WB	DL	8	12	10.7	64.0	10.7
SUB-TOTALS =								10.7	64.0	10.7
TOTALS =								18.7	124.0	18.7
CHAMPAIGN CO. I-72 URBAN TOTALS =								19.0	124.0	19.0
USE =								19.0	124.0	19.0

I-72 EASTBOUND CLASS A 16" PATCHES												
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200645 TYPE II 16.0" (SQ YD)	44200647 TYPE IV 16.0" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	RURAL	1624+68.31	175.390	EB	DL	8	12	10.7	0.0	64.0	0.0	10.7
SUB-TOTALS =								10.7	0.0	64.0	0.0	10.7
I-72 WESTBOUND CLASS A 16" PATCHES												
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200645 TYPE II 16.0" (SQ YD)	44200647 TYPE IV 16.0" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	RURAL	1620+61.75	175.313	WB	DL	100	12	0.0	133.3	248.0	50.0	133.3
CHAMPAIGN	RURAL	1610+74.39	175.126	WB	DL	20	12	0.0	26.7	88.0	10.0	26.7
SUB-TOTALS =								0.0	160.0	336.0	60.0	160.0
TOTALS =								10.7	160.0	400.0	60.0	170.7
CHAMPAIGN CO. I-72 RURAL TOTALS =								11.0	160.0	400.0	60.0	171.0
USE =								11.0	160.0	400.0	60.0	171.0

I-74 EASTBOUND CLASS A 17" PATCHES													
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200633 TYPE I 17.0" (SQ YD)	44200637 TYPE II 17.0" (SQ YD)	44200643 TYPE IV 17.0" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	URBAN	1593+52.53	173.240	EB	DL	6	12	0.0	8.0	0.0	60.0	0.0	8.0
CHAMPAIGN	URBAN	1620+03.09	173.742	EB	DL	6	12	8.0	8.0	0.0	60.0	0.0	8.0
SUB-TOTALS =								8.0	16.0	0.0	120.0	0.0	16.0
I-74 WESTBOUND CLASS A 17" PATCHES													
COUNTY	URBAN/ RURAL	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	44200633 TYPE I 17.0" (SQ YD)	44200637 TYPE II 17.0" (SQ YD)	44200643 TYPE IV 17.0" (SQ YD)	44213200 SAW CUTS (FT)	44213204 TIE BARS 3/4" (EACH)	44213000 PATCHING REINFORCEMENT (SQ YD)
CHAMPAIGN	URBAN	1519+13.01	171.831	WB	DL	30	12	0.0	0.0	40.0	108.0	15.0	40.0
SUB-TOTALS =								0.0	0.0	40.0	108.0	15.0	40.0
TOTALS =								8.0	16.0	40.0	228.0	15.0	56.0
CHAMPAIGN CO. I-74 URBAN TOTALS =								8.0	16.0	40.0	228.0	15.0	56.0
USE =								8.0	16.0	40.0	228.0	15.0	56.0

FILE NAME =	USER NAME = goreas	DESIGNED -	REVISED -
c:\pw\work\p\dot\goreas\d0400102\0570A01	l-sh-t-cover-soq-schedules.dgn	DRAWN -	REVISED -
\$MODELNAME\$	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 6/26/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET 2 OF 4 SHEETS STA. TO STA.

*VARIOUS **CHAMPAIGN, DOUGLAS, & VERMILION

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	D5 CM PATCHING 2015-2	**	32	29
CONTRACT NO. 70A81				
ILLINOIS FED. AID PROJECT				