

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				ROADWAY 0004 S.N.	BRIDGE 0011 S.N.
28200200	FILTER FABRIC	SQ YD	4,315	4,083	232
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	839	839	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	2,200	2,200	
40600300	AGGREGATE (PRIME COAT)	TON	5	5	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	124	124	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174	174	
40600990	TEMPORARY RAMP	SQ YD	232	232	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	843	843	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	266	266	
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	42	42	
44000100	PAVEMENT REMOVAL	SQ YD	300	300	
44004250	PAVED SHOULDER REMOVAL	SQ YD	378	378	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	90	90	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	331	331	