

SEEDING SCHEDULE									
LOCATION			AREA	SEEDING, CLASS 2	NIT. FERTILIZER NUTRIENT	PHOS. FERTILIZER NUTRIENT	POT. FERTILIZER NUTRIENT	AGR. GRND. LIMESTONE	MULCH, METHOD 2
STA	TO	STA	SQ. FT.	ACRE	POUND	POUND	POUND	TON	ACRE
1712+50.00	TO	1713+00.00	1,000	0.02	2.07	2.07	2.07	0.05	0.02
1713+00.00	TO	1713+50.00	2,375	0.05	4.91	4.91	4.91	0.11	0.05
1713+50.00	TO	1714+00.00	3,600	0.08	7.44	7.44	7.44	0.17	0.08
1714+00.00	TO	1714+50.00	4,175	0.10	8.63	8.63	8.63	0.19	0.10
1714+50.00	TO	1715+00.00	3,575	0.08	7.39	7.39	7.39	0.16	0.08
1715+00.00	TO	1715+50.00	3,225	0.07	6.66	6.66	6.66	0.15	0.07
1715+50.00	TO	1716+00.00	3,650	0.08	7.54	7.54	7.54	0.17	0.08
1716+00.00	TO	1716+50.00	4,200	0.10	8.68	8.68	8.68	0.19	0.10
1716+50.00	TO	1717+00.00	4,300	0.10	8.88	8.88	8.88	0.20	0.10
1717+00.00	TO	1717+50.00	4,150	0.10	8.57	8.57	8.57	0.19	0.10
1717+50.00	TO	1718+00.00	3,875	0.09	8.01	8.01	8.01	0.18	0.09
1718+00.00	TO	1718+50.00	3,750	0.09	7.75	7.75	7.75	0.17	0.09
1718+50.00	TO	1719+00.00	3,725	0.09	7.70	7.70	7.70	0.17	0.09
1719+00.00	TO	1719+50.00	3,675	0.08	7.59	7.59	7.59	0.17	0.08
1719+50.00	TO	1720+00.00	3,900	0.09	8.06	8.06	8.06	0.18	0.09
1720+00.00	TO	1720+50.00	2,300	0.05	4.75	4.75	4.75	0.11	0.05
1720+50.00	TO	1720+66.30	196	0.004	0.40	0.40	0.40	0.01	0.00
1721+83.70	TO	1722+00.00	236	0.01	0.49	0.49	0.49	0.01	0.01
1722+00.00	TO	1722+50.00	1,825	0.04	3.77	3.77	3.77	0.08	0.04
1722+50.00	TO	1723+00.00	3,050	0.07	6.30	6.30	6.30	0.14	0.07
1723+00.00	TO	1723+50.00	2,975	0.07	6.15	6.15	6.15	0.14	0.07
1723+50.00	TO	1724+00.00	2,875	0.07	5.94	5.94	5.94	0.13	0.07
1724+00.00	TO	1724+50.00	2,625	0.06	5.42	5.42	5.42	0.12	0.06
1724+50.00	TO	1725+00.00	2,425	0.06	5.01	5.01	5.01	0.11	0.06
1725+00.00	TO	1725+50.00	2,475	0.06	5.11	5.11	5.11	0.11	0.06
1725+50.00	TO	1726+00.00	2,325	0.05	4.80	4.80	4.80	0.11	0.05
1726+00.00	TO	1726+50.00	2,000	0.05	4.13	4.13	4.13	0.09	0.05
1726+50.00	TO	1727+00.00	1,725	0.04	3.56	3.56	3.56	0.08	0.04
1727+00.00	TO	1727+50.00	1,300	0.03	2.69	2.69	2.69	0.06	0.03
1727+50.00	TO	1728+00.00	1,200	0.03	2.48	2.48	2.48	0.06	0.03
1728+00.00	TO	1728+50.00	1,850	0.04	3.82	3.82	3.82	0.08	0.04
1728+50.00	TO	1729+00.00	2,600	0.06	5.37	5.37	5.37	0.12	0.06
1729+00.00	TO	1729+50.00	1,750	0.04	3.62	3.62	3.62	0.08	0.04
1729+50.00	TO	1730+00.00	350	0.01	0.72	0.72	0.72	0.02	0.01
TOTAL =				2.1	184	184	184	4.1	2.1

EROSION CONTROL SCHEDULE						
LOCATION				PERIMETER EROSION BARRIER (FOOT)	AGGREGATE DITCH CHECKS (TON)	
STAGE I	STA	TO	STA			
	1714+58.00			LT	6	
	1714+75.00			LT	6	
	1714+75.00	TO	1716+00.00	LT	129	
	1718+00.00			LT	6	
	1720+00.00			LT	6	
	1722+20.00			LT	6	
	1723+00.00			LT	6	
	1724+00.00			LT	6	
	1725+00.00			LT	6	
	1726+00.00			LT	6	
	1727+00.00			LT	6	
STAGE II						
	1713+00.00			RT	6	
	1714+05.00			RT	6	
	1716+00.00			RT	6	
	1717+00.00			RT	6	
	1717+50.00			RT	6	
	1718+00.00			RT	6	
	1719+00.00			RT	6	
	1720+00.00			RT	6	
	1720+40.00			RT	6	
	1724+50.00	TO	1729+50.00	RT	500	
TOTAL=				629	114	

TEMPORARY TRAFFIC CONTROL SCHEDULE

LOCATION	STA.				TEMP CONC BAR (FOOT)	RELOCATE TEMP CONC BAR (FOOT)	IMP ATTEN TEMP (FULL RE-DIRECT, NARROW) TEST LVL 3 (EACH)	IMP ATTEN RELOCATE (FULL RE- DIRECT, NARROW) TEST LVL 3 (EACH)	
STAGE I	1717+87.50	LT					1		
	1717+87.50	LT	TO	1719+00.00	CL	112.5			
	1719+00.00	CL	TO	1723+50.00	CL	450.0			
	1723+50.00	CL	TO	1724+62.50	LT	112.5			
	1724+62.50	LT					1		
STAGE II	1717+87.50	RT						1	
	1717+87.50	RT	TO	1719+00.00	CL	112.5			
	1719+00.00	CL	TO	1723+50.00	CL	450.0			
	1723+50.00	CL	TO	1724+62.50	RT	112.5			
	1724+62.50	RT						1	
TOTALS =						675.0	675.0	2	2

STRIPING SCHEDULE

LOCATION				PAINT PAVEMENT MARKING - LINE 5" (FOOT)	
Sta	to	Sta		WHITE	YELLOW
1715+00.00	to	1727+50.00	RT	1250	
1715+00.00	to	1727+50.00	CL		313
1715+00.00	to	1727+50.00	LT	1250	
TOTAL =				2,813	