

SCHEDULE CONTINUED

MAINLINE PATCHING											
QUANTITY AFTER MILLING OPERATION - CONC PAVT, 9"					44200541 CLASS A PATCHES, TY II, 9 IN	44200545 CLASS A PATCHES, TY III, 9 IN	44200547 CLASS A PATCHES, TY IV, 9 IN	44213200 SAW CUTS	44213000 PATCHING REINFORCE- MENTS	44213204 TIE BARS, 3/4"	
MILE MARKER	LANE	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	
128.4	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
128.4	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
128.2	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
127.7	SBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
127.7	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
127.5	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
127.4	SBDL	30	12	40.0	--	--	40.0	108.0	40.0	28.0	
127.3	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
127.3	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
RAMP STA AT I-55 AND I-155 SPLIT (SB LANES ONLY)											
127.2	SBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
127.2	SBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
127.1	SBDL	8	12	10.7	10.7	--	--	64.0	10.7	--	
127.0	SBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
126.9	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
126.8	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
126.6	SBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
126.6	SBDL	7	12	9.3	9.3	--	--	62.0	9.3	--	
RESUME I-55 STATIONING											
126.5	SBML	5	12	6.7	6.7	--	--	58.0	6.7	--	
126.4	SBML	8	12	10.7	10.7	--	--	64.0	10.7	--	
126.4	SBML	6	12	8.0	8.0	--	--	60.0	8.0	--	
126.4	SBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
126.4	SBML	8	12	10.7	10.7	--	--	64.0	10.7	--	
I-155 MAINLINE NORTHBOUND LANES											
0.0	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.0	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.0	NBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.0	NBDL	10	12	13.3	13.3	--	--	68.0	13.3	--	
0.0	NBPL	7	12	9.3	9.3	--	--	62.0	9.3	--	
0.1	NBDL	8	12	10.7	10.7	--	--	64.0	10.7	--	
0.1	NBPL	8	12	10.7	10.7	--	--	64.0	10.7	--	
0.2	NBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.2	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.2	NBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.2	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.3	NBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.3	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.4	NBDL	10	6	6.7	6.7	--	--	44.0	6.7	--	
0.5	NBDL	6	6	4.0	4.0	--	--	36.0	4.0	--	
0.6	NBDL	5	12	6.7	6.7	--	--	58.0	6.7	--	
0.7	NBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.7	NBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
I-155 MAINLINE SOUTHBOUND LANES											
0.7	SBDL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.7	SBPL	6	12	8.0	8.0	--	--	60.0	8.0	--	
0.2	SBDL	8	6	5.3	5.3	--	--	40.0	5.3	--	
TOTAL:					1181	151	163	9488	1496	234	

ANTICIPATED MAINLINE PATCHING - SPECIFIC LOCATION AND PATCH SIZE TO BE DETERMINED BY ENGINEER ON FIELD - VARIOUS OPERATIONS											
LOCATION WITH 3.25" OF BINDER BEFORE MILLING OPERATION - CONC PAVT + HMA OVERLAY, 12"					44200577 CLASS A PATCHES, TY II, 12 IN	44200581 CLASS A PATCHES, TY III, 12 IN	44200583 CLASS A PATCHES, TY IV, 12 IN	44213200 SAW CUTS	44213000 PATCHING REINFORCE- MENTS	44213204 TIE BARS, 3/4"	
MILE MARKER	LANE	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	
VARIOUS	VARIOUS	VARIOUS	VARIOUS	VARIOUS	352.0	132.0	88.0	3303.4	520.9	81.5	
VARIOUS	VARIOUS	VARIOUS	VARIOUS	VARIOUS	440.0	220.0	132.0	4129.3	651.0	101.8	
TOTAL:					792	352	220	7433	1172	183	

ANTICIPATED MAINLINE PATCHING - SPECIFIC LOCATION AND PATCH SIZE TO BE DETERMINED BY ENGINEER ON FIELD - VARIOUS OPERATIONS											
LOCATION WITH 4.75" BINDER BEFORE MILLING OPERATION - CONC PAVT + HMA OVERLAY, 14"					44200620 CLASS A PATCHES, TY II, 14 IN	44200624 CLASS A PATCHES, TY III, 14 IN	44200628 CLASS A PATCHES, TY IV, 14 IN	44213200 SAW CUTS	44213000 PATCHING REINFORCE- MENTS	44213204 TIE BARS, 3/4"	
MILE MARKER	LANE	LENGTH FOOT	WIDTH FOOT	AREA SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	EACH	
VARIOUS	VARIOUS	VARIOUS	VARIOUS	VARIOUS	48.0	18.0	12.0	450.5	71.0	11.1	
VARIOUS	VARIOUS	VARIOUS	VARIOUS	VARIOUS	60.0	30.0	18.0	563.1	89.0	13.9	
TOTAL:					108	48	30	1014	160	25	

•• SUMMARY:

44213200 SAW CUTS (FOOT)		44213204 TIE BARS, 3/4" (EACH)	
ITEM	QUANTITY	ITEM	QUANTITY
CLASS A, 9" PATCHES	9488	CLASS A, 9" PATCHES	234
CLASS A, 12" PATCHES	7433	CLASS A, 12" PATCHES	183
CLASS A, 14" PATCHES	1014	CLASS A, 14" PATCHES	25
CLASS B, 11" PATCHES	2734	CLASS B, 11" PATCHES	260
TOTAL:	20668	TOTAL:	703

44213000 PATCHING REINFORCEMENTS (SQ YD)	
ITEM	QUANTITY
CLASS A, 9" PATCHES	1496
CLASS A, 12" PATCHES	1172
CLASS A, 14" PATCHES	160
TOTAL:	2828