

PAVEMENT MARKINGS

NOTE 1: 10' SKIP @ 40' OFFSET NOTE 2: 3' SKIP @ 12' OFFSET NOTE 3: CENTERLINE 4" - 4' @ 40' OFFSET NOTE 4: EDGE LINE: 4" - 4' @ 100' OFFSET			70300100		70301000	78004200	78004220	78004240	78004250	78004280		78009005		78009000	78009008	78009024	7830072	
			SHORT TERM PAVT MARKING CENTERLINE (NOTE 3) 2 APP. FOOT	SHORT TERM PAVT MARKING CENTERLINE (NOTE 4) 1 APP. FOOT	WORK ZONE PAVT MARK REM 1 APP. SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LETTERS & SYMBOLS WHITE SQ FT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 5" WHITE (NOTE 1 & 2) FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 8" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 12" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" WHITE FOOT	PRE PLAST PAVT MARK, TY B - INLAID - LINE 24" WHITE FOOT	MOD URETH PAVT MARK - LINE 5" YELLOW MEDIAN FOOT	MOD URETH PAVT MARK - LINE 5" WHITE OUTSIDE FOOT	MOD URETH PAVT MARK- LETTERS & SYMBOLS WHITE SQ FT	MOD URETH PAVT MARK- LINE 8" WHITE FOOT	MOD URETH PAVT MARK- LINE 24" WHITE FOOT	X7830072 GROOVE FOR RECESSED PAVT MARK 6" FOOT
LOCATION	LENGTH	AREA																
STATION TO STATION	FOOT	SO FT																
I-55 NORTHBOUND (R001)																		
STA 380+57.30	TO STA 398+95.66	MAINLINE (OUT & MED)	1,838.36	367.67	73.53	85.79		919.18				1,838.36	1,838.36					3,676.72
STA 391+94.94	TO STA 398+95.66	GORE (2)	700.72	1,401.44		233.57			1,401.44									
GORE CHEVERONS			401.00	802.00		133.67				401.00								
STA 398+95.66	TO STA 445+62.78	MAINLINE (OUT & MED)	4,667.12	933.42	186.68	217.80		1,166.78				4,667.12	4,667.12					9,334.24
STA 426+04.36	TO STA 432+93.28	GORE (2)	688.92	1,377.84		229.64			1,377.84									
STA 432+93.28	TO STA 438+43.24	GORE SHORT-DASH	549.96						137.49									
I-55 NB TO I-155 NB (R002, R002A)																		
STA 01+15.00	TO STA 29+64.42	MAINLINE (OUT & MED)	2,849.42	569.88	113.98	132.97		663.79				2,849.42	2,849.42					5,698.84
STA 15+56.98	TO STA 17+51.25	ON SN 054-0051	194.27	38.85	7.77	9.07								48.57				
I-155 SB TO I-55 SB (R006)																		
STA 37+95.69	TO STA 46+30.87	MAINLINE (OUT & MED)	835.18		33.41	11.14								835.18				835.18
STA 37+95.69	TO STA 46+30.87	MAINLINE (OUT & MED)	835.18		33.41	11.14		835.18										
MAINLINE CHEVERONS			264.00	528.00		88.00					264.00							
STA 46+30.87	TO STA 56+81.57	GORE (2)	1,050.70	2,101.40		350.23		2,101.40										
GORE CHEVERONS			659.00	1,318.00		219.67				659.00								
I-155 SB TO I-55 NB (R004)																		
STA 18+22.37	TO STA 34+44.61	MAINLINE (OUT & MED)	1,622.24		64.89	21.63						1,622.24	1,622.24					3,244.48
I-55 SB TO I-155 NB (R005, A004))																		
STA 458+12.97	TO STA 460+84.53	GORE SHORT DASH	271.56					67.89										
STA 454+04.00	TO STA 458+12.97	GORE (2)	408.97	817.94		136.32		817.94										
GORE CHEVERONS			191.00	382.00		63.67				191.00								
I-55 SOUTHBOUND (A003/4)																		
STA 379+87.59	TO STA 387+19.56	MAINLINE (OUT & MED)	731.97	146.39	29.28	34.16		365.99				731.97	731.97					1,463.94
STA 387+19.56	TO STA 397+69.99	MAINLINE (OUT & MED)	1,050.43	210.09	42.02	49.02		262.61				1,050.43	1,050.43					2,100.86
I-55 SOUTHBOUND (R003)																		
STA 43+41.63	TO STA 00+00.00	MAINLINE (OUT & MED)	4,341.63	868.33	173.67	202.61		1,085.41				4,341.63	4,341.63					8,683.26
I-55 SOUTHBOUND (A004)																		
STA 452+88.81	TO STA 465+56.26	MAINLINE (OUT & MED)	1,267.45	253.49	50.70	59.15		316.86				1,267.45	1,267.45					2,534.90
I-55 NORTHBOUND (A004)																		
STA 465+56.26	TO STA 533+29.96	MAINLINE (OUT & MED)	6,773.70	1,354.74	270.95	316.11		1,693.43				6,773.70	6,773.70					13,547.40
STA 533+29.96	TO STA 540+35.82	SN 054-0053 (OUT & MED)	705.86	141.17	28.23	32.94						705.86	882.33					
STA 540+35.82	TO STA 554+83.65	MAINLINE (OUT & MED)	1,447.83	289.57	57.91	67.57		361.96				1,447.83	1,447.83					2,895.66
STA 554+83.65	TO STA 562+33.87	SN 054-0055 (OUT & MED)	750.22	150.04	30.01	35.01						750.22	937.78					
STA 562+33.87	TO STA 575+70.23	MAINLINE (OUT & MED)	1,336.36	267.27	53.45	62.36		334.09				1,336.36	1,336.36					2,672.72
STA 575+70.23	TO STA 577+98.08	SN 054-0057 (OUT & MED)	227.85	45.57	9.11	10.63						227.85	284.81					
STA 577+98.08	TO STA 696+51.35	MAINLINE (OUT & MED)	11,853.27	2,370.65	474.13	553.15		2,963.32				11,853.27	11,853.27					23,706.54
STA 696+51.35	TO STA 702+43.49	SN 054-0061 (OUT & MED)	592.14	118.43	23.69	27.63						592.14	740.17					
STA 702+43.49	TO STA 727+56.90	MAINLINE (MED)	2,513.41	502.68	100.54	117.29		628.35				2,513.41						2,513.41
STA 706+75.62	TO STA 716+48.41	MAINLINE (OUT)	972.79	194.56	38.91	45.40		243.20					972.79					972.79
STA 727+56.90	TO STA 790+97.12	BK MAINLINE (OUT & MED)	6,340.22	1,268.04	253.61	295.88		1,585.06				6,340.22	6,340.22					12,680.44
STA 184+93.00	AH TO STA 281+03.71	MAINLINE (OUT & MED)	9,610.71	1,922.14	384.43	448.50		2,402.68				9,610.71	9,610.71					19,221.42
STA 281+03.71	TO STA 284+20.20	SN 054-0063 (OUT & MED)	316.49	63.30	12.66	14.77						316.49	395.61					
STA 284+20.20	TO STA 456+39.65	MAINLINE (OUT & MED)	17,219.45	3,443.89	688.78	803.57		4,304.86				17,219.45	17,219.45					34,438.90
STA 456+39.65	TO STA 457+59.39	SN 054-0065 (OUT & MED)	119.74	23.95	4.79	5.59						119.74	149.67					
STA 457+59.39	TO STA 478+95.06	MAINLINE (OUT)	2,135.67	427.13	85.43	99.66						2,135.67						2,135.67
STA 457+59.39	TO STA 519+65.39	MAINLINE (MED)	6,206.00	1,241.20	248.24	289.61		1,551.50				6,206.00						6,206.00
STA 485+71.68	TO STA 508+27.13	MAINLINE (OUT)	2,255.45	451.09	90.22	105.25							2,255.45					2,255.45
STA 519+65.39	TO STA 590+00.00	MAINLINE (OUT & MED)	7,034.61	1,406.92	281.38	328.28		1,758.65				7,034.61	7,034.61					14,069.22

SCHEDULE CONTINUED ON NEXT 2 SHEETS

FILE NAME = c:\pw\work\p1dot\sparksgw\2041-sht-schedule.dgn			USER NAME = sparksgw	DESIGNED - DMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 100.0000' / 1" =			CHECKED -	REVISED -							LOGAN	108	21		
PLOT DATE = Jul-14-2014 03:36:47PM			DATE -	REVISED -			SCALE:	SHEET 14	OF	SHEETS	STA.	TO	STA.	CONTRACT NO. 72D41	
ILLINOIS FED. AID PROJECT															