

PREFORMED PLASTIC PAVEMENT MARKING			
LOCATION IL 4 (VETERANS PKWY.)	PREF PL PAVE MARK TY-B - LINE 24" (FT)		PREF PL PAVE MARK TY-B - LET & SYM (SQ FT)
	STOP BAR WHITE		WHITE
IL 4 (VETERANS PARKWAY)			
SOUTH BOUND			
LT TL	STA. 139+16.64		15.6
RT TL	STA. 139+70.19		15.6
LT TL	STA. 140+34.02		15.6
RT TL	STA. 141+10.19		15.6
LT TL	STA. 141+53.86		15.6
RT TL	STA. 142+35.19		15.6
LT TL	STA. 142+73.73		15.6
LT TL	STA. 142+99.67	13.0	
STA. EQ. 154+43.19 BK = 154+05.70 AH			
LT TL	STA. 168+76.35		15.6
RT TL	STA. 169+39.78		15.6
LT TL	STA. 169+92.20		15.6
RT TL	STA. 170+73.44		15.6
LT TL	STA. 171+10.54		15.6
RT TL	STA. 171+99.33		15.6
RT TL	STA. 172+30.94	20.0	
LT TL	STA. 172+26.32		15.6
LT TL	STA. 172+53.91	12.0	
SB	STA. 172+49.27	22.0	
LT TL	STA. 181+50.52		15.6
LT TL	STA. 182+78.23		15.6
RT TL	STA. 183+61.28		15.6
LT TL	STA. 184+00.44		15.6
RT TL	STA. 184+79.10		15.6
LT TL	STA. 185+25.09		15.6
LT TL	STA. 185+46.01	13.0	
RT TL	STA. 185+90.75		15.6
SB	STA. 186+12.20	49.0	
SUB-TOTAL		129.0	327.6
IL 4 (VETERANS PARKWAY)			
NORTH BOUND			
LT TL	STA. 143+92.43	13.0	
LT TL	STA. 144+18.88		15.6
RT TL	STA. 144+73.42		15.6
LT TL	STA. 145+38.51		15.6
RT TL	STA. 145+99.66		15.6
LT TL	STA. 146+58.88		15.6
RT TL	STA. 147+38.42		15.6
LT TL	STA. 147+74.72		15.6
STA. EQ. 154+43.19 BK = 154+05.70 AH			
LT TL	STA. 173+53.07	12.0	
ML	STA. 173+53.79	26.0	
LT TL	STA. 173+78.87		15.6
RT TL	STA. 173+79.93	15.0	
RT TL	STA. 174+05.00		15.6
LT TL	STA. 174+85.65		15.6
RT TL	STA. 175+22.93		15.6
LT TL	STA. 176+07.71		15.6
RT TL	STA. 176+57.56		15.6
LT TL	STA. 177+29.57		15.6
ML	STA. 186+48.72	64.0	
RT TL	STA. 186+75.43		15.6
LT TL	STA. 187+08.10	12.0	
LT TL	STA. 187+32.59		15.6
RT TL	STA. 187+65.85		15.6
LT TL	STA. 188+48.90		15.6
RT TL	STA. 188+55.26		15.6
LT TL	STA. 189+72.21		15.6
LT TL	STA. 190+98.13		15.6
SUB-TOTAL		142.0	327.6

PREFORMED PLASTIC PAVEMENT MARKING			
LOCATION IL 4 (VETERANS PKWY.)	PREF PL PAVE MARK TY-B - LINE 24" (FT)		PREF PL PAVE MARK TY-B - LET & SYM (SQ FT)
	STOP BAR WHITE		WHITE
CAMP LINCOLN RD.			
WB	STA. 48+99.52	20.0	
EB	STA. 49+41.55		22.3
WB	STA. 49+83.08		22.3
EB	STA. 50+23.85	20.0	
SUB-TOTAL		40.0	44.6
BRUNS LN.			
EB RT TL	STA. 99+47.58		15.6
EB ML	STA. 99+66.90		26.0
EB ML	STA. 99+84.55	12.0	
EB RT TL	STA. 100+00.60	15.0	
WB RT TL	STA. 100+93.24	15.0	
WB ML	STA. 101+16.75	10.0	
WB ML	STA. 101+30.87		26.0
WB RT TL	STA. 101+87.71		15.6
SUB-TOTAL		52.0	83.2
PALOMINO RD.			
WB RT TL	STA. 20+28.09	18.0	
WB ML	STA. 20+45.11	13.0	
EB ML	STA. 22+00.72	13.0	
EB RT TL	STA. 22+20.19	16.0	
SUB-TOTAL		60.0	0.0
TOTAL		423.0	783.0

MODIFIED URETHANE PAVEMENT MARKING					
LOCATION STATION TO STATION FAP 662/67 IL 4/ IL 97	LENGTH (FT)	MODIFIED URETHANE PAVEMENT MARK - LINE 5"			MOD URETHANE PAVE MARK - LINE 12"
		EDGE LINE (FT)		CENTER LINE (FT)	CHEVRON (FT)
IL 4 (VETERANS PARKWAY)					
SOUTH BOUND					
STA. 117+00.00 TO STA. 142+35.19	2,535.2	WHITE	YELLOW	YELLOW	
STA. 141+54.50 TO STA. 143+23.50	169.0		361.6		59.3
STA. 143+93.36 TO STA. 154+43.19	1,049.8	1049.8	1058.7		45.0
STA. EQ. 154+43.19 BK = 154+05.70 AH					
STA. 154+05.70 TO STA. 172+58.57	1,852.9	1768.9	1853.5		
STA. 171+01.60 TO STA. 172+69.25	167.7		362.3		77.3
STA. 173+63.36 TO STA. 186+13.08	1,249.7	1189.6	1207.8		65.0
STA. 183+94.01 TO STA. 186+22.15	228.1		508.7		152.6
STA. 186+99.88 TO STA. 198+70.93	1,171.1	1095.2	1177.7		62.0
STA. EQ. 198+70.93 BK = 198+88.77 AH					
STA. 198+88.77 TO STA. 216+50.00	1,761.2	1,761.2	1,761.2		
SUB-TOTAL		9,765.8	10,900.2		461.2
IL 4 (VETERANS PARKWAY)					
NORTH BOUND					
STA. 117+00.00 TO STA. 142+93.68	2,593.7	2593.7	2609.6		46.0
STA. 143+65.28 TO STA. 145+46.10	180.8		385.9		59.1
STA. 143+87.65 TO STA. 154+43.19	1,055.5	965.0	1055.6		
STA. EQ. 154+43.19 BK = 154+05.70 AH					
STA. 154+05.70 TO STA. 172+39.16	1,833.5	1774.9	1856.3		67.5
STA. 173+31.80 TO STA. 175+01.72	169.9		365.8		84.0
STA. 173+45.44 TO STA. 185+49.30	1,203.9	1021.7	1205.9		65.0
STA. 186+76.04 TO STA. 188+54.48	178.4		429.9		139.3
STA. 186+51.21 TO STA. 198+70.93	1,219.7	1216.7	1173.1		
STA. EQ. 198+70.93 BK = 198+88.77 AH					
STA. 198+88.77 TO STA. 216+50.00	1761.2	1761.2	1761.2		
SUB-TOTAL		9,333.2	10,843.2		460.9
CAMP LINCOLN RD					
STA. 47+34.27 TO STA. 49+40.03	205.8	411.3			328.5
STA. 49+88.35 TO STA. 51+71.71	183.4	364.1			293.8
SUB-TOTAL		775.4			622.3
BRUNS LN					
STA. 98+48.84 TO STA. 100+02.26	153.4	402.8			271.6
STA. 101+02.71 TO STA. 102+01.61	98.9	312.6			169.4
SUB-TOTAL		715.5			441.0
PALOMINO RD					
STA. 19+51.33 TO STA. 20+04.20	52.9	287.5			187.4
STA. 22+37.05 TO STA. 22+96.64	59.6	272.6			189.0
SUB-TOTAL		560.1	0.0	376.4	
COLOR SUB-TOTAL		21,150.0	21,743.4	1,439.7	922.1
TOTAL			44,333.1		922.1

SHORT-TERM PAVEMENT MARKING					
LOCATION STATION TO STATION	LENGTH (FT)	SPACING	NUMBER OF APPLICATIONS	SHORT-TERM PAVE MARK (FT)	WORK ZONE PAVE MARK REM (SQ FT)
FAP 662/67 (IL 4/97)					
IL 4 (VETERANS PKWY)					
STA. 117+00.00 TO STA. 154+43.19	3743.2	4' / 40'	2	1513.3	252
STA. EQ. 154+43.19 BK = 154+05.70 AH					
STA. 154+05.70 TO STA. 198+70.93	4465.2	4' / 40'	2	1802.1	300
STA. EQ. 198+70.93 BK = 198+88.77 AH					
STA. 198+88.77 TO STA. 216+50.00	1761.2	4' / 40'	2	720.5	120
		TOTAL		4,035.9	672