

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STATE URBAN FOUR-LANE ROADWAY 100% STATE 0014	0044 DRAINAGE SYSTEM 100% CITY OF DECATUR
35400540	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 14"	SQ YD	87	87	
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	485	485	
40600990	TEMPORARY RAMP	SQ YD	122	122	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	96	96	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	1481	1481	
44000100	PAVEMENT REMOVAL	SQ YD	1481	1481	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1512	1512	
44004000	PAVED DITCH REMOVAL	FOOT	615	615	
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	102	102	
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	20	20	
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	87		87
44213100	PAVEMENT FABRIC	SQ YD	1481	1481	
50102400	CONCRETE REMOVAL	CU YD	220.6	220.6	