

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				BRIDGE				
				0014				
				060-0104				
				100% STATE				
50300100	FLOOR DRAINS	EACH	6	6				
50300225	CONCRETE STRUCTURES	CU YD	94.8	94.8				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	913.0	913.0				
50300260	BRIDGE DECK GROOVING	SO YD	1595	1595				
50300300	PROTECTIVE COAT	SO YD	2648	2648				
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5150	5150				
50500505	STUD SHEAR CONNECTORS	EACH	6,960	6,960				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	220,170	220,170				
50800515	BAR SPLICERS	EACH	184	184				
51100100	SLOPE WALL 4 INCH	SO YD	4	4				
51500100	NAME PLATES	EACH	1	1				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	190	190				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	20	20				
52100520	ANCHOR BOLTS, 1"	EACH	40	40				

14

(S) SEE SPECIAL PROVISIONS * SPECIALITY ITEM

FILE NAME *	USER NAME * USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES FAI 55			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
P:\102166-12\60-2HB-2 76G10 FAI 55\CADD	Sheets\0876G10-ent-500.dgn	DRAWN - MCM	REVISED -					55	60-2HB-2	MADISON	52	5
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -		SCALE:	SHEET 2 OF 5 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = 7/11/2014	DATE - 6/30/14	REVISED -						CONTRACT NO. 76G10			