

GUARDRAIL SCHEDULE																
LOCATION				LENGTH	RT/LT	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKERS DIRECT APPLIED	CONCRETE CURB, TYPE B	EARTH EXCAVATION	CURB REMOVAL	GUARDRAIL REMOVAL	
STA	TO	STA	FOOT			FOOT	EACH	EACH	EACH	EACH	EACH	FOOT	CU YD	FOOT	FOOT	
152+93.95	TO	156+18.95	325.00	RT		275.0	1	1		5	1					340
156+69.39	TO	164+06.89	737.50	LT		687.5	1	1		10	1					598
162+00.27	TO	167+75.27	575.00	RT		525.0	1	1		8	1					370
179+35.47	TO	181+60.97*	325.00	LT		275.0	1	1		5	1					332
179+30.07	TO	182+80.07	350.00	RT		300.0	1	1		5	1					291
183+54.09	TO	185+91.59	237.50	RT		187.5	1	1		3	1					130
190+89.95	TO	193+14.95	225.00	RT		175.0	1	1		3	1					142
195+06.97	TO	198+31.97	325.00	LT		275.0	1	1		5	1					229
214+53.77	TO	217+78.77	325.00	RT		275.0	1	1		5	1					268
264+27.11	TO	268+02.11	375.00	LT		325.0	1	1		5	1					114
362+80.87	TO	363+87.12	106.25	RT		12.5	1		1	2	1	15.6	0.3			109
362+80.87	TO	363+87.12	106.25	LT		12.5	1		1	2	1	129.0	2.4	138		109
365+37.53	TO	367+31.28	193.75	RT		100.0	1		1	3	1	15.6	0.3			41
365+37.53	TO	367+31.28	193.75	LT		100.0	1		1	3	1	15.6	0.3			116
TOTAL						3525.0	14	10	4	64	14	176	3.3	138		3189

* INCLUDES 100' OF RADIUS GUARDRAIL

GENERAL NOTE: THE COST OF FILLING THE CURB REMOVAL AREA ALONG THE WINGWALL WITH CONCRETE SHALL BE INCLUDED IN THE COST OF CONCRETE CURB, TYPE B.

PAINT PAVEMENT MARKING SCHEDULE											
LOCATIONS				PAINT PAVEMENT MARKING-LINE 4" YELLOW SKIP DASH	PAINT PAVEMENT MARKING-LINE 4" YELLOW	PAINT PAVEMENT MARKING-LINE 4" DOUBLE YELLOW	PAINT PAVEMENT MARKING-LINE 4" WHITE SKIP DASH	PAINT PAVEMENT MARKING-LINE 4" WHITE EDGE LINE	PAINT PAVEMENT MARKING- LETTERS AND SYMBOLS	PAINT PAVEMENT MARKING-LINE 24" WHITE STOP BAR	PAINT PAVEMENT MARKING-LINE 12" CROSS WALK
				FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT
FROM	179+89	TO	198+42	470	1,853	3,707	470	3,707	188	72	142
FROM	296+82	TO	306+91	260	1,009	2,019	260	2,019	159	96	
FROM	363+87	TO	365+38	40	150	301	40	301	0	0	
CALCULATED QUANTITY:				770	3,013	6,026	770	6,026	347	168	142
PLAN QUANTITY:						16,605			347	168	142

GENERAL NOTE: PAVEMENT MARKING QUANTITIES ARE BASED ON PREVIOUS JOB, MICROFILM AND FIELD MEASUREMENTS. ALL SHALL BE ASSUMED TO BE APPROXIMATE THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

NO PASSING ZONE AND GENERAL STRIPING SHOULD BE RE-ESTABLISHED BY RESIDENT ENGINEER.
LETTERS & SYMBOLS: TURN ARROWS AREA IS 15.6 SQ FT EACH